#### **Errata**

Title & Document Type: 6212B/6214B/6216B/6218B DC Power Supply Operating

and Service Manual

Manual Part Number: 5950-1928

**Revision Date: November 1982** 

#### **About this Manual**

We've added this manual to the Agilent website in an effort to help you support your product. This manual provides the best information we could find. It may be incomplete or contain dated information, and the scan quality may not be ideal. If we find a better copy in the future, we will add it to the Agilent website.

#### **HP References in this Manual**

This manual may contain references to HP or Hewlett-Packard. Please note that Hewlett-Packard's former test and measurement, life sciences, and chemical analysis businesses are now part of Agilent Technologies. The HP XXXX referred to in this document is now the Agilent XXXX. For example, model number HP8648A is now model number Agilent 8648A. We have made no changes to this manual copy.

#### **Support for Your Product**

Agilent no longer sells or supports this product. You will find any other available product information on the Agilent Test & Measurement website:

#### www.agilent.com

Search for the model number of this product, and the resulting product page will guide you to any available information. Our service centers may be able to perform calibration if no repair parts are needed, but no other support from Agilent is available.





## DC POWER SUPPLY BENCH SERIES MODELS 6212B, 6214B, 6216B, 6218B

## OPERATING AND SERVICE MANUAL FOR SERIALS:

MODEL 6212B, 2240A-02411 AND ABOVE MODEL 6214B, 2238A-08181 ANF ABOVE MODEL 6216B, 2230A-19951 AND ABOVE MODEL 6216B, 2236A-09831 AND ABOVE

\*For instrument with serial numbers above those listed a change page may be included.

HP Part No. 5950-1928 Microfiche Part No. 5950-7929 Printed: November 1982

#### SAFETY SUMMARY

The following general safety precautions must be observed during all chases of operation, service, and repair of this instrument. Failure to comply with these precautions or with specific warnings clowhere in this manual violates safety star, dards of design, manufacture, and intended use of the instrumen. Hewlett-Packard Company assumes no liability for the customer's failure to comply with these requirements.

#### BEFORE APPLYING POWER.

Verify that the product is set to match the available line voltage and the correct fuse is installed.

#### **GROUND THE INSTRUMENT.**

This product is a Safety Class 1 Instrument (provided with a protective earth terminal). To minimize shock hazard, the instrument chassis and cabinet must be connected to an electrical ground. The instrument must be connected to the ac power supply mains through a three-conductor power cable, with the third wire firmly connected to an electrical ground (safety ground) at the power outlet, For instruments designed to be hard-wired to the ac power lines (supply mains), connect. the protective earth terminal to a protective conductor before any other connection is made. Any interruption of the protective (grounding) conductor or disconnection of the protective earth terminal will cause a potential shock hazard that could result in personal injury. If the instrument is to be energized via an external autotransformer for voltage reduction, be certain that the autotransformer common terminal is connected to the neutral (earthed pole) of the ac power lines (supply mains).

## INPUT POWER MUST BE SWITCH CONNECTED.

For instruments without a built-in line switch, the input power il hes must contain a switch or another adequate means for disconnecting the instrument from the ac power lines (supply mains).

## DO NOT OPERATE IN AM EXPLOSIVE ATMOSPHERE.

Do not operate the instrument in the presence of flammable guses or fumes.

#### KEEP AWAY FROM LIVE CIRCUITS.

Operating personnel must not remove instrument covers. Component replacement and internal adjustments must be made by qualified service personnel. Do not replace components with power cable connected. Under certain conditionc, dangerous voltages may exist even with the power cable removed. To avoid injuries, always disconnect power, discharge circuits and remove external voltage sources before touching components.

#### DO NOT SERVICE OR ADJUST ALONE.

Do not attempt internal service or adjustment unless another person, capable of rendering first aid and resuscitation, is present.

#### DO NOT EXCEED INPUT RATINGS.

This instrument may be equipped with a line filter to reduce electromagnetic interference and must be connected to a properly grounded receptacle to minimize electric shock hazard. Operation at line voltages or frequencies in excess of those stated on the data plate may cause leakage currents in excess of 5.0 mA peak.

#### SAFETY SYMBOLS.



instruction manual symbol: the product will be marked with this symbol when it is necessary for the user to refer to the instruction manual (refer to Table of Contents).



Indicates hazardous voltages.



or 🕹

Indicate earth (ground) terminal.



The WARNING sign denotes a hazard. It calls attention to a procedure, practice, or the like, which, if not correctly performed or adhered to, could result in personal injury. Do not proceed beyond a WARNING sign until the indicated conditions are fully understood and met.

CAUTION

The CAUTION sign denotes a hazard. It cells i attention to an operating procedure, or the like, which, if not correctly performed or adhered to, could result in damage to or destruction of part or all of the product. Do not proceed beyond a CAUTION sign until the indicated conditions are fully understood and met.

## DO NOT SUBSTITUTE PARTS OR MODIFY INSTRUMENT.

Because of the danger of introducing additional hazards, do not install substitute parts or perform any unauthorized modification to the instrument. Return the instrument to a Hewlett-Packard Sales and Service Office for service and repair to ensure that safety features are maintained.

Instruments which uppear damaged or defective should be made inoperative and secured against unintended operation until. I they can be repaired by qualified service personnel.

## Section I GENERAL INFORMATION

#### 1-1 DESCRIPTION

- 1-2 This power supply is completely transistorized and suitable for either bench or relay rack operation. It is a ompact, well-regulated, Constant Voltage/Constant Current supply that will furnish full rated output voltage at the maximum rater output current or can be continuously adjusted throughout the output range. The front panel CURRENT control can be used to establish the output current limit (overload or short circuit) when the supply is used as a constant voltage source and the VOLTAGE controls can be used to establish the voltage limit (celling) when the supply is used as a constant current source. The supply will automatically crossover from constant voltage to constant current operation and vice versa if the output current or voltage exceeds these preset limits.
- 1-3 Eliher the positive or negative output terminal may be grounded or the power supply can be operated floating at up to a maximum of 300 volts off ground,
- 1-4 A single meter is used to measure either output voltage or output current in volts of mA. The voltage or current range is selected by the METER SELECTION switch on the front panel.

#### 1-5 SPECIFICATIONS

,1-6 Detailed specifications for the power supply are given in Table 1-1.

#### 1-7 OPTIONS

1-8 Options are factory modifications of a standard instrument that are requested by the customer. The following options are available for the instrument covered by this manual. Where necessary, detailed coverage of the options is included throughout the manual.

#### Option No.

#### Description

228

230 V, 50-400 Hz, Single-Phase Output. Factory nodification consists of reconnecting the input transformer for 230 Vac operation. Refer to Section II for further details.

910

One additional operating and cervice manual shipped with the, power supply.

#### 1-9 ACCCESSORIES

1-10 The accessories listed in the following chart may be ordered with the power supply or separately from your local Hewlett-Packard field sales office (refer to list at rear of manual for addresses).

HP Part No.

Description

14521B

3 1/2" High Rack Kit for mounting up to three BENCH supplies. (Refer to Section II for details.)

## 1-11 !NSTRUMENT AND MANUAL IDENTIFICATION

- 1-12 Hewlett-Packard power supplies are identified by a two-part serial number. The first part is the serial number prefix, a number-letter combination that denotes the date of a significant design change and the country of manufacture. The first two digits of the prefix indicate the year (20 = 60, 21 = 81, etc.), the second two digits indicate the week, and the letter "A" designates the USA as the country of manufacture. The second part of the serial number is a different sequential number assigned to each power supply, starting with 00101.
- 1-13 If the serial number on your instrument does not, agree with those on the title page of this manual, a yellow change sheet supplied with the manual defines the difference between your instrument, and the instrument described by this manual.

## 1-14 ORDERING ADDITIONAL MANUALS

1-15 One manual is shipped with each power supply. Additional manuals may be purchased from your local Hewlett-Packard field office (see list at rear of this manual for addresses). Specify the model number, serial number prefix, and HP stock number provided on the title page.

#### INPUT:

6212B	6214B
115 Vac, ±10%, 48- 440 Hz, 0.29A, 28W	115 Vag. ± 10%, 48- 440 Hz, 0,3A, 28W
6216B	6218B
115 Vac, ±10%, 48- 440 Hz, 0.25A, 26W	115 Vac, ±10%, 48-440 Hz, 0.25A, 26W
MITTALIT.	and the second second

#### OUTPUT:

6212A	6214B
0 to 100 Vdc, 0 to	0 to 10 Vdc, 0 to
0.1 A	1A 1
6215B	6213B
0 to 25 Vdc, 0 to	0 to 50 Vdc, 0 to
0.4 A	0.2 A

#### LOAD REGULATION:

Constant Voltage – Less than 4 mV (8 mV, 6212B) for a load turrent change equal to the current rating of the supply

Constant Current - Less than 500 µA for a load voltage change equal to the voltage rating of the supply.

#### LINE REGULATION:

Constant Voltage – Less than 4 mV for ±10% change in the nominal line voltage at any output voltage and current within rating.

Constant Current-Less than 500  $\mu$ A for a  $\pm$  10% change in the normal line voltage at any output voltage and current within rating.

#### **RIPPLE AND NOISE:**

Constant Voltage – Less than 200  $\mu$ V rms/1 mV p-p (dc to 20 Mhz).

Constant Current – Less than 150  $\mu$ A p-p (dc to 20 MHz).

#### **TEMPERATURE RANGES:**

Operating: 0° to 55° C. Storage: -40° to +75° C.

#### TEMPERATURE COEFFICIENT:

Constant Voltage – Less than 5.02'6 + 1 mV output change per degree centigrade change in ambient following 30 minutes warm-up.

Constant Current - Lese than (see table) output change per degree centigrade change in ambient following 30 minutes warm-up.

6212A	_	0.5 mA
6214B	-	6 mA
62168	-	2 mA
6218B	_	1 mA

#### STABILITY:

Constant Voltage – Less than 0.1% +5 mV total drift for 8 hours following 30 minutes warm-up at constant ambient, constant line voltage, and constant load.

Constant Current – Less than (see table) total drift for 8 hours following 30 minutes warm-up at constant ambient, constant line voltage, and constant load,

6212B	_	1.3 mA
6214B	-	15 mA
6216B	-, ,	 5 mA
62188 -	_	2.5 mA

#### TRANSIENT RECOVERY TIME:

Less than 50 µsec for output voltage recovery in constant voltage operation to within 15 mV of the nominal output voltage following a change in output current equal to the current rating of the supply.

#### **OVERLOAD PROTECTION:**

A fixed current limiting circuit protects the power supply for all overloads including a direct short circuit placed across the output terminals in constant voltage operation.

#### METER:

The front panel meter can be used as a voltmeter or an ammeter.

#### CUTPUT CONTROLS:

Concentric coarse and fine voltage controls and concentric coarse and fine current controls set desired output voltage/current. Meter switch selects voltage or current.

#### **OUTPUT TERMINALS:**

Three "five-way" output terminals are provided on the front panel. They are isolated from the chassis and either the positive or negative terminal may be connected to the chassis through a separate ground terminal.

#### COOLING:

Convection cooling is employed. The supply has no moving parts.

#### SIZE:

See Figure 2-1.

#### WEIGHT:

4.75 lbs./1,2 kg. net. 6.75 lbs./3,1 kg. shipping.

#### FINISH:

Dark gray.

#### POWER CORD:

A 3-wire, 5 foot (1,52 cm) power cord is provided with each unit.

#### Section II INSTALLATION




Figure 2-1. Outline Diagram

#### 2-7 INITIAL INSPECTION

2-2 Before shipment, this instrument was inspected and found to be free of mechanical and electrical defects. As soon as the instrument is unpacked, inspect for any damage that may have occurred in transit. Save all packing materials until the inspection is completed. If damage is found, file claim with carrier immediately. Hewlett-Packard Sales and Service office should be notified as soon as possible.

#### 2-3 Mechanical Check

2-4 This check should confirm that there are no

broken knobs or connectors, that the cabinet and panel surfaces are free of dents and scretches, and that the meter is not scratched or cracked.

#### 2-5 Electrical Check

2-6 The instrument should be checked against its electrical specifications. Section V includes an "incabinet" performance check to verify proper instrument operation.

#### 2-7 INSTALLATION DATA

2-8 The instrument is shipped ready for bench operation. It is necessary only to connect the instrument to a source of power and it is ready operation.

#### 2-9 Location

2-10 This instrument is air cooled. Sufficient space should be allotted so that a free flow of cooling air can reach the rear of the instrument when it is in operation. It should be used in an area where the ambient temperature does not exceed 55° C.

#### 2-11 Outline Diagram

2-12 Figure 2-1 illustrates the outline shape and dimensions of Models 6211B through 6218B.

#### 2-13 Rack Mounting

2-14 This instrument may be rack mounted separately or with a maximum of two other BENCH Series supplies as shown in Figure 2-2. The units are placed in the Rack Mounting Frame. The Rack Mounting Frame is then fastened to the rack frame.




Figure 2-2. Rack Kit with three BENCH supplies.

#### 2-15 INPUT POWER REQUIREMENTS

2-16 This power supply may be operated continuously from either a nominal 115 volt or 230 volt 50-400 Hz power source. The unit as shipped from the factory, is wired for 115 volt operation. The input power required when operated from a 115 volt power source at full load is:

Model	Input Current	Input Power
6212B	0.29A	28W
6214B	0.29A	28W
6217B	0,25A	26W
6218B	0,25A	26W

## 2-17 Connections for 230 Volt Operation (Figure 2-3)

- 2-18 Normally, the two primary windings of the input transformer are connected in parallel for operation from 115 volt source. To convert the power supply to operation from a 230 volt source, the power transformer windings are connected in series as follows:
  - a. Unplug the line cord and remove the top cover as described in Pulgraph 5-3,
  - b. Remove the jumpers between taps 4-2 and 3-1. Solder a jumper between taps 3-2 on the input power transformer T1, see Figure 2-3.
  - c. Replace existing fuse with 0.5 ampere, 230 volt duse.
  - d. Replace existing line cord plug with a standard 230 volt plug.

#### 2-19 Power Cable

2-20 To protect operating personnel, the National Electrical Manufacturers Association (NEMA) recommends that the instrument panel and cabinet be grounded. This instrument is equipped with a three conductor power cable. The third conductor is the ground conduc-

tor and when the cable is plugged into an appropriate receptacle, the instrument is grounded. The offset pin on the power cable three-prong connector is the ground connection.




Figure 2-3. Input Power Transformer, Connections

2-21 To preserve the protection feature when operating the instrument from a two contact outlet, use a three-prong to two-prong adapter and connect the green lead on the adapter to ground.

#### 2-22 REPACKAGING FOR SHIPMENT

2-23 To insure safe shipment of the instrument, it is recommended that the package designed for the instrument be used. The original packaging material is reusable. If it is not available, contact your local Hewlett-Packard field office to obtain the materials. This office will also furnish the address of the nearest service office to which the instrument can be shipped. Be sure to attach a tag to the instrument which specifies the owner, model number, full serial number, and service required, or a brief description of the trouble.

## Section III OPERATING INSTRUCTIONS

## 3-1 TURN-ON C

KOUT

3-2 The following cher \_\_t procedure describes the use of the front panel control and indicators illustrated in Figure 3-1 and ensures that the supply is operational:




Figure 3-1. Front Panel Controls and Indicators.

- Set AC loggle switch (1) upward to on position; indicator (2) should light.
- b. Set METER SELECTION switch (3) to VOLTS position.
- c. Turn coarse (4) and fine (5) VOLTAGE controls fully ccw to ensure that output decreases to 0V, then turn the VOLTAGE controls fully cw to ensure that output voltage increases to the maximum rated output voltage.
- d. Set METER SELECTION switch (3) to mA position and short circuit (+) and (-) output terminals.
- e. Turn coarse (6) and fine (7) CURRENT controls fully ccw and then fully cw to ensure that the output current reaches zero and maximum rated output.
- $f_{\rm tot}$  . Remove short and connect load to output  $\mathbb{R}^{n_{\rm tot}}(f_{\rm tot})$  terminals,

#### 3-3 OPERATION

3-4 The power supply can be operated as a single unit (normal operation), in parallel, or in series. The output of the supply can be floated up to 300 volts off ground.

#### 3-5 Constant Voltage

- 3-6 To select a constant voltage output, proceed as follows:
  - Turn-on power supply and adjust VOLTAGE controls for desired output voltage (output terminals open).
- b. Short output terminals and adjust CURRENT controls for maximum output current allowable (current limit), as determined by load conditions. If a load change causes the current limit to be exceeded, the power supply will automatically crossover to constant current output at the present current limit and the output voltage will drop proportionately. In setting the current limit, allowance must be made for high peak current which can cause un vanted cross-over. (Refer to paragraph 3-20),

#### 3-7 CONSTANT CURRENT

- 3-8 To select a constant current output, proceed as follows:
  - a. Short output terminals and adjust CURRENT controls for desired output current.
  - b. Open output terminals and adjust VOLTAGE controls for maximum output voltage allowable (voltage limit), as determined by load conditions. If a load change causes the voltage limit to be exceeded, the power supply will automatically crossover to constant voltage output at the preset voltage limit and the output current will drop proportionately. In setting the voltage limit, allowance must be made for high peak voltages which can cause unwanted crossover. (Refer to paragraph 3-20).

#### 3-9 CONNECTING LOADS

3-10 Each load should be connected to the power supply output terminals using separate pairs of connecting wires. This will minimize mutual coupling effects between loads and will retain full advantage of the low output impedance of the power supply. Each pair of connecting wires should be as short as possible and twisted or shielded to reduce noise pickup. (If shield is used, connect one end to power supply ground terminal and leave the other end unconnected.)

3-11 If load considerations require that the output power distribution terminals be remotely located from the power supply, then the power supply output terminals should be connected to the remote distribution terminals via a pair of twisted or shielded wires and each load separately connected to the remote distribution terminals.

## 3-12 Operation of Supply Beyond Rated Output.

3-13 The shaded area on the front panel meter face indicates the amount of output voltage or current that is available in excess of the normal rated output. Although the supply can be operated in this shaded region without being damaged, it cannot be guaranteed to meet all of its performance specifications. However, if the line voltage is maintained above 115 Vac, the supply will probably operate within its specifications.

#### 3-14 OPTIONAL OPERATING MODES

#### 3-15 Series Operation

3-16 Normal Series Connections. Two or more power supplies can be operated in series to obtain a higher voltage than that available from a single supply. When this connection is used, the output voltage is the sum of the voltages of the individual supplies. Each of the individual supplies must be adjusted in order to obtain the total output voltage. The power supply contains a protective diode connected internally across the output which protects the supply if one power supply is turned off while its series partner(s) is on.

#### 3-17 Parallel Operation

3-18 Two or more power supplies can be connected in parallel to obtain a total output current greater than that available from one power supply. The total output current is the sum of the output currents of the individual power supplies. The output of each power supply can be set separately. The output voltage controls of one power supply should be set to the desired output voltage; the other power supply should be set for a slightly larger output voltage, The supply set to the lower output voltage will act as a constant voltage source; the supply set to the higher output will act as a current limit source, dropping its output voltage until it equals that of the other supply. The constant voltage source will deliver only that fraction of its total rated output current which is necessary to 'fulfill the total current demand.

## 3-19 SPECIAL OPERATING CONSIDERATIONS

#### 3-20 Pulse Loading

3-21 The power supply will automatically cross over from constant-voltage to constant-current operation in response to an increase (over the preset limit) in the output current. Although the preset limit may be set higher than the average output current, high peak currents (as occur in pulse loading) may exceed the preset current limit and cause crossover to occur. If this crossover limiting is not desired, set the preset limit for the peak requirement and not the average.

#### 3-22 Output Capacitance

3.23 An internal capacitor, across the output terminals of the power supply, helps to supply high-current pulses of short duration during constant voltage operation. Any capacitance added externally will improve the pulse current capability, but will decrease the safety provided by the current limiting circuit. A high-current pulse may damage load components before the average output current is large enough to cause the current limiting circuit to operate,

#### 3-24 Reverse Current Loading

- 3-25 Active loads connected to the power supply may actually deliver a reverse current to the power supply during a portion of its operating cycle. An external source cannot be allowed to pump current into the supply without loss of regulation and possible damage to the output capacitor. To avoid these effects, it is necessary to proload the supply with a dummy load resistor so that the power supply delivers current 'hrough the entire operating cycle of the load device.
- 3-26 Reverse Voltage Protection. A diode is connected across the output terminals with reverse polarity. This diode protects the output electrolytic capacitors and the series regulator transistors from the effects of a reverse voltage applied across the output terminals. For example, in series operation of two supplies, if the AC is removed from one supply, the diode prevents damage to the unenergized supply which would otherwise result from a reverse polarity voltage.
- 3-27 Since series regulator transistors or driver transistors cannot withstand reverse voltage, another diode is connected across the series transistor. This diode protects the series transistors in parallel or Auto-Parallel operation if one supply of the parallel combination is turned on before the other.

## Section IV PRINCIPLES OF OPERATION




Figure 4-1. Block Diagram.

#### 4-1 OVERALL DESCRIPTION

- 4-2 The major circuits of the power supply are shown on the overall block diagram, Figure 4-1.
- 4-3 The input AC line voltage is stepped down by the power transformer and applied to the rectifier and filter. The rectifier-filter converts the AC input to raw DC which is fed to the positive output terminal via series regulator Q7 and current sampling resistor R33. The regulator, part of the feedback loop, is made to elter its conduction to maintain a constant output voltage or current. The
- voltage developed across the current sampling resistor is the input to the constant current input amplifier. The constant voltage input amplifier obtains its input by sampling the output voltage of the supply.
- 4.4 Any changes in output voltage or current are detected in the constant voltage or constant current input circuit, amplified by the e or amplifier, and driver and applied to the series regulator in the correct phase and amplitude to counteract the change in output voltage or current.
- 4-5 Two input amplifiers are included in a CV/CC

supply, one for controlling output voltage, the other for controlling output current. Since the constant voltage amplifier tends to achieve zero output impedance and alters the output current whenever the load resistance changes, while the constant current comparison amplifier rauses the output impedance to be infinite and changes the output voltage in response to any load resistance change, it is obvious that the two comparison amplifiers cannot operate simultaneously. For any given value of load resistance, the power supply must act either as a constant voltage source or as a constant current source-it cannot be both; transfer between these two modes is accomplished at a value of load resistance equal to the ratio of the output voltage control cetting to the output current control setting.

Figure 4-2 shows the output characteristic of a CV/CC power supply. With no load attached (R<sub>L</sub> =  $\infty$ ), IOUT = 0, and EOUT = ES, the front panel voltage control setting. When a load resistence is applied to the output terminals of the power supply, the output current increases, whole the output voltage remains constant; point D thus represents a typical constant voltage operating point. Further decreases in load resistance are accompanied by further increases in IOUT with no change in the output voltage until the output current reaches Is, a value equal to the front panel current control setting. At this point the supply automatically changes its mode of pepration and becomes a constant current source; still further decreases in value of load resistance are accompanied by a drop in the supply output voltage with no accompanying change in the output current value. Thus, point B represents a typical constant current operating point. Still further decreases in the load resistance result




Figure 4-2. Operating Locus of a Cycle Power

in output voltage decreases with no change in output current, until finally, with a short circuit across the output load terminals, IOUT = IS and EOUT = 0.

4-7 By gradually changing the load resistance from a short circuit to an open circuit the operating locus of Figure 4-2 will be traversed in the opposite direction.

Full protection against any overload condition is inhe ent in the Constant Voltage/Constant Current design principle since there isn't any load condition that can cause an output which lies outside the operating locus of Figure 4-2. Whether one is primarily concerned with constant voltage or constant current operation, the proper choice of ES and is insures optimum protection for the load device as well as full protection for the power supply itself.

- 4-8 The line connecting the origin with any ope; uting point of the locus of Figure 4-2 has a slope which is proportional to the value of load resistance connected to the output terminals of the supply. One cun define a "critical" or "crossover" value of load resistance  $R_C = E_S/I_S$ ; adjustment of the front panel voltage and current controls permits this "crossover" resistance  $R_C$  to be set to any desired value from 0 to  $\infty$ . If  $R_L$  is greater than  $R_C$ , the supply in constant voltage operation, while if  $R_L$  is less than  $R_C$ , the supply is in constant current operation.
- 4-9 The reference circuit provides stable reference voitages which are used by the constant voltage/current input circuits for comparison purposes. The meter circuit provides an indication of output voltage or current for both operating modes.
- 4-10 Diode CR14 is connected across the output terminals in reverse polarity. It protects the output electrolytic capacitor and the series regulator transistor from the effects of a reverse voltage applied across the output terminals. For example, in series operation of two supplies, if the AC is removed from one supply, the diode prevents damage to the unenergized supply.

# 4-11 DETAILED CIRCUIT ANALYSIS (Refer to Figures 7-1 and 7-2, Schematic Diagram)

#### 4-12 Feedback Loop

4-13 The feedback loop functions continuously to keep the output voltage constant during constant voltage operation, and the output current constant during constant current operation. For purposes of this discussion, assume that the unit is in constant voltage operation and that the programming resistors R10A and B have been adjusted so that the supply is yielding the desired output voltage. Further assume that the output voltage instan-

taneously rises (increases) due to a variation (decrease) in the external load circuit.

- 4-14 Note that the change may be in the form of a slow rise in the cutput voltage or a positive going AC signal. An AC signal is coupled to Q1 through capacitor C1 and a DC voltage is coupled to Q1 through R10.
- 4-15 The increase in output voltage causes the voltage at the base of Q1 to decrease (go negative). Q1 now decreases its conduction and its collector voltage rises. The positive going error voltage is amplified and inverted by Q4 and fed to the base of series transistor Q7 via emitter follower Q5. The negative going input causes Q7 to decrease its conduction so that it drops more of the supply voltage, and reduces the output voltage to its original level. (62128 only, zener diode VR9 limits the voltage swing across Q5 and Q7 and, thus, minimizes the dissipation of Q5).
- 4-16 If the external load resistance is decreased to a certain crossover point as discussed in Paragraph 4-6 the cutput current increases until transistor Q12 begins to conduct. During this time, the output voltage has also decreased to a level so that the base of Q1 is at a high positive potential. With Q1 in full conduction, its collector voltage decreases by the amount necessary to back bias OR gate diode CR5 and the supply is now in the constant current mode of operation. The operation of the feedback loop during the constant current operating mode is similar to that occurring during constant voltage operation except that the input to the constant current input amplifier is obtained from the current sampling resistor R33.

#### 4-17 Series Regulator

4-18 The series regulator consists of transistor stage Q7 (see schematic at rear of manual). The regulator serves as a series control element by altering its conduction so that the output voltage or current is kept constant. The conduction of the transistor is controlled by the feedback voltage obtained from the error amplifier. Diode CR7 protects the series transistor against reverse voltages that could develop during parallel operation, if one supply is turned on before the other,

#### 4-19 Constant Voltage Input Amplifier

4-20 This circuit consists of programming resistor R10A and B, and a differential amplifier stage (Q1, Q2, and associated components). The constant voltage input amplifier continuously compares a fixed reference voltage with a portion of the output voltage and, if a difference exists, produces an error voltage whose amplitude and phase is proportional to the difference. The error output is fed back to the series regulator, through

an OR gate and the driver and error amplifiers. The error voltage changes the conduction of the series regulator which, in turn, alters the output voltage so that the difference between the two input voltages applied to the differential amplifier is reduced to zero. The above action maintains the output voltage constant.

4-21 Stage Q2 of the differential amplifier is connected to a common (+S) potential through impedance equalizing resistor R6. Resistor(s) Z1B (and R2, for the 6212B) are used to zero bias the input stage, offsetting minor base-to-emitter voltage differences in Q1 and Q2. The base of Q1 is connected to a summing point at the junction of the programming resistor and the current pullout resistor, R12. Instantaneous changes in output voltage result in an increase or decrease in the summing point potential. Q1 is then made to conduct more or less. in accordance with the summing point voltage charge. The resultant output error voltage is fed back to the series regulator via OR-gate diode CR5 and the remaining components of the feedback loop. Resistor R1, in series with the base of G1, limits the current through the programming resistor during rapid voltage turn-down. Diodes CR1 and CR2 form a limiting network which prevent excessive voltage excursions from over driving stage Q1. Capacitor C1, shunting the programming resistors increases the high frequency gain of the input amplifier.

#### 4-22 Constant Current Input Amplifier

- 4-23 This circuit is similar in appearance and operation to the constant voltage input circuit. It consists basically of the current programming resistors R11A and B, and a differential amplifier stage (Q12, Q13, and associated components).
- 4-24 The constant current input amplifier continuously compares a fixed reference voltage with the voltage drop across current sampling resistor R33. If a difference exists, The differential amplifier produces an error voltage which is proportional to this difference. The remaining components in the feedback loop (amplifiers and series regulator) function to maintain the drop across the current sampling resistor, and consequently the output current, at a constant value. R14 and R57 compensate for the current drawn by the meter when in constant current mode by drawing an equivalent amount of current when output is shorted for current setting thus assuring proper current to load.
- 4-25 Stage Q13 is connected to a common (+S) potential through impedance equalizing resistor R43. Resistor Z1G is used to zero bias the input stage, offsetting minor base-to-emitter voltage differences in Q12 and Q13. Instantaneous changes in output current on the positive line are felt at the base of Q12. Stage Q12 varies its conduction in accordance with the polarity of the

change at the summing point. The change in conduction of Q12 also varies the conduction of Q13 due to the coupling effects of the common emitter resistor Z1H. The error voltage is taken from the collector of Q13 and fed back to the series regulator through QR-gate diode CR6 and the remaining components of the feedback loop. The error voltage then varies the conduction of the regulator so that output current is maintained at the proper level.

4-26 Capacitor C4, in conjunction with Z1K helps stabilize the feedback loop. Diode CR20 limits voltage excursions on the base of Q12.

## 4-27 Voltage Clamp Circuit

4-28 During constant current operation the constant voltage programming resistors R10A and £ are a shunt load across the output terminals of the power supply. If the output voltage varies, the current through these resistors would tend to change resulting in an output current change. The clamp circuit is a return path for the voltage programming current, the current that normally flows through the programming resistors. The circuit maintains the current into the base of Q1 constant, thus eliminating the error due to shunting effects of the constant voltage programming resistors.

4-29 The voltage divider, Z1E, Z1F, and VR2 back biases CR3 and Q3 during constant voltage operation. When the power supply goes into constant current operation, CR3 becomes forward biased by the collector voltage of Q1. This results in conduction of Q3 and the clamping of the summing point at a potential only slightly more negative than the normal constant voltage potential. Clamping this voltage at approximately the same potential that exists in constant voltage operation, results in a constant voltage across, and consequently a constant current through pullout resistor R12.

### 4-30 Driver and Error Amplifier

4-31 The error and driver amplifiers amplify the error signal from the constant voltage input circuit to a level sufficient to drive the series regulator transistor. Amplifier Q4 also receives a current limiting input if CR6, the current limiting diode, becomes forward biased.

4-32 Stage Q4 contains a feedback equalizer network, C3 and R17, which provides for high frequency roll off in the loop gain in order to stabilize the feedback loop.

## 4-33 Reference Regulator Circuit

4-34 The reference regulator circuit is a separate power supply similar to the main supply. It provides stable reference voltages which are used throughout the unit. The reference voltages are all derived from smoothed do obtained from the full wave rectifier (CR10 and CR11) and filter capacitor C5. The -6.2 V and -12.4 V reference voltages are derived from VR1 v nich is a second do source regulating at 12.4 Vdc. Current for VR1 is supplied by the (-) side of C5 and flows through VR1, the base-emitter junction of Q7, R20, and back to the positive side of C5.

4-35 The base-emitter junction of Q11 is held constant by 6.2 V zener diode VR7 which regulates line voltage changes that alter the voltage across C5. Thus Q11 is a constant current source feeding 7.5 V zener diode VR4, 4 V diode VR5, and 6.2 V temperature-compensated zener diode VR6.

4-36 Resistors R30 and VR8 form a voltage divider across the stable 12.4 volts developed by VR1. The base-emitter junction of Q9 is therefore held constant by the voltage developed across VR8. Thus Q9 provides a constant current to zener diode R3 which regulates the -6.2 V cource.

#### 4-37 Meter Circuit

4-38 This circuit provides indication of output voltage or current. With METER SELECTION switch S2 set to V position, the meter is in series with R54, and R52 across the output of the supply.

4-39 With METER SELECTION switch S2 set to mA position, the meter is connected in series with R52 and R53 across current sampling resistor R33. CURRENT ADJ potentiometer R52 is adjusted for full scale deflection with a full load connected to the output terminals. Resistors R55, R14, and R57 are connected across the current sampling resistor R33 when S2 is set to V position. It prevents the current sampling resistor from indicating an erroneous current by simulating the meter circuit, which is connected across the current sampling resistor in the current mode.



## Section V MAINTENANCE

#### 5-1 INTRODUCTION

5-2 Upon receipt of the power supply, the perior mance check (Paragraph 5-8) should be made. This ctyck is suitable for incoming inspection, if a fault is detected in the power supply while making the performance check or during normal operation, proceed to the troubleshooting procedures (Paragraph 5-57). After troubleshooting and repair (Paragraph 5-65), perform any necessary adjustments and calibrations (Paragraph 5-67). Before returning the power supply to normal operation, repeat the performance check to ensure that the fault has been properly corrected and that no other faults exist.

## 5-3 COVER REMOVAL AND REPLACEMENT

- 5-4 To remove the top and bottom covers, proceed as follows:
  - a. Insert a small screen over in each of the four notches at the frunt of the unit a the top and bottom. Push the screwdriver under the front panel and gently pry toward the front of the unit to release the holding mechanism.
  - b. Pull the front panel forward until it clears

- the top and bottom covers.
- c. Remove the rear cover by repeatinng step a.
- d. Pull the rear cover until it clears the top and bottom covers. Then lift off the top cover and lift out the bottom cover.
- 5.5 To replace the top and bottom cover, proceed as follows:
  - Place the unit into the bottom cover (identifed by the four protruding feet) and align the heat sink into the track in the bottom cover.
  - b. Place the top cover over the unit and align the track over the heat sink.
  - While holding the covers together at the rear of the unit, carefully push on the rear panel.
  - d. Position the front panel so that the two slotted ears at the bottom of the panel align with the printed wiring boards.
  - e. Carefully push on the front panel.

#### 5-6 TEST EQUIPMENT REQUIRED

5-7 Table 5-1 lists the test equipment required to perform the various procedures described in this Section.

Table 5-1. Test Equipment Required

TYPE	REQUIRED CHARACTERISTICS (MIN)	USE	RECOMMENDED MODEL
Precision Voltmeter	Sensitivity: 1mV full scale (min.). Input impedance: 10 megohms (min.).	Measure dc voltages; calibra- tion procedures	(HP) 3456
Variable Voltage Transformer	Range: 90-130 or 200-260 volts. Equipped with voltmeter accurate within 1 volt.	Vary ac Input	••••
AC Voltmeter	Accuracy: 2%. Sensitivity: 1 mV full scale deflection (min.).	Measure ac voltages and ripple	(HP) 3400
Oscilloscope	Sensitivity: 100 μV/cm. Differential input.	Display transient response waveforms	(HP) 1800 plus 1801A and 1821A plug in's
Oscillator	Range: 5 Hz to 600 Hz. Accuracy: 2%. Output: 10 V rms.	Impedance checks	(HP) 200CD

Table 5-1, Test Equipment Required (Continued).

TYPE	REQUIRED CHARACTERISTICS (MIN)	USE	RECOMMENDED MODEL
DC Voltmeter	Accuracy:1%. Input resistance: 20,000 ohms/Volt (min.).	Measure dc voltages	(HP) 3456 or 3466
Repetitive Load Switch	Rate: 60-400 Hz, 2 µsec rise and fall time.	Measure transient response	See Figure 5-7.
Tasistive Loads	Values: See Paragraphs 5-16 and 5-47.	Power supply load resistors	•••
Current Sam- pling Resistor	See R33 in Parts List (Section VI).	Measure current; calibrate meter	••••
Resistor	1 KΩ ±1%, 10 Watt.	Measure impedance	
Capacitor	500 μF, 50 W Vdc.	Measure impedance	

#### **5-8 PERFORMANCE TEST**

The following test can be used as an incoming inspection check and appropriate portions of the test can be repeated either to check the operation of the instrument after repairs or for periodic maintainence tests. The tests are performed using normal single phase input power source. If the correct result is not obtained for a particular check, do not djust any controls; proceed to troubleshooting (Paragraph 5-57).

#### **5-10** Constant Voltage Tests

- 5-11 The measuring device must be connected as close to the output terminals as possible when measuring the output impedance, transient response, regulation, or ripple of the power supply in order to achieve valid measurements. A measurement made across the load includes the impedance of the leads to the load and such lead lengths can easily have an impedance several orders of magnitude greater than than the supply impedance, thus invalidating the measurement.
- 5-12 The monitoring device should be connected as shown in Figure 5-1. Note that the monitoring leads are connected at A, not B, as shown in Figure 5-1. Failure

to connect the measuring device at A will result in a measurement that includes the resistance of the leads between the output terminals and the point of connection. When measuring the constant voltage performance specifications, the current controls should be set well above the maximum output current which the supply will draw, since the onset of constant curent action will cause a drop in output voltage, increased ripple, and other performance changes not properly ascribed to the constant voltage operation of the supply.




Figure 5-1. Front Panel Terminal Connections.

## 5-13 Reted Output and Meter Accuracy.

## **5-14** Voltage. To check the output voltage, proceed as follows:

- a. Connect load resistor (RL), indicated in Figure 5-2, across the output terminals of supply.
- b. Connect voltmeter accross (+) and (-) terminals of supply observing correct polarity.
- c. Set METER SELECTION switch to VOLTS and turn on supply.
- d. Adjust VOLTAGE controls until front panel meter indicates exactly the maximum rated output voltage.
- Voltmeter should indicate maximum rated output voltage within ±4%.




Figure 5-2. CV Load Regulation, Test Setup.

#### 5-15 Load Regulation.

**Definition:** The change EOUT in the static value of do output voltage resulting from a change in load resistance from open circuit to a value which yeilds maximum rated output current (or vice versa).

5-16 To check the constant voltage load regulation, proceed as follows:

- Connect test setup as shown in Figure 5-3.
- b. Set METER SELECTIOON switch to mA position.

- Turn on supply and adjust VOLTAGE controls until front panel meter indicates maximum rated output current.
- d. Read and record voltage indicated on voltmeter.
- e. Disconnect load resistor.
- Reading on voltmeter should not vary from reading recorded in step d by more than 8mVdc.

#### 5-17 Line Regulation.

**Definition:** The change, EQUT, in the static value of dc output voltage resulting from a change in ac input voltage over the specified range from low line (-10%) to high line (+10%), or from high line to low line.

#### 5-18 To test the line regulation, proceed as follows:

- Connect variable auto transformer between input power source and power supply power input.
- b. Connect test setup shown in Figure 5-2.
- Adjust variable auto transformer for low line ac input.
- d. Set METER SELECTION switch to VOLTS position.
- e. Turn on supply and adjust VOLTAGE controls until front panel meter indicates exactly the maximum rated output voltage.
- f. Read and record voltage indicated on voltmeter.
- g. Adjust variable auto transformer for high VAC input.
- Reading on voltmeter should not vary from reading recorded in step f by more than 4 mVdc.

#### 5-19 Ripple and Noise.

Definition: The residual AC voltage which is superimposed on the DC output of a regulated power supply. Ripple and noise may be specified and measured in terms of its RMS or (preferably) peak-to-peak value.

Ripple and noise measurement can be made at any input AC line voltage combined with any DC output voltage and load current within rating.

5-20 The amount of ripple and noise that is present on the power supply output is measured either in terms of the RMS or (preferably) peak-to-peak value. The peak-to-peak measurement is particularly important for applications where noise spikes could be detrimental to a sensitive lead, such as logic circuitry. The RMS measurement is not an ideal representation of the noise, since fairly high output noise spikes of short duration could be

present in the ripple and not appreciably increase the RMS value.

5-21 The technique used to measure high frequency noise or "spikes" on the output of a power supply is more critical than the low frequency ripple and noise measurement technique; therefore the former is discussed separately in Paragraph 5-29.

Ripple and Noise Measurement. Figure 5-3 shows an incorrect method of measuring p-p ripple. Note that a continuous ground loop exists from the third wire of the input power cord of the supply to the third wire of the input power cord of the oscilloscope via the grounded power supply case, the wire between the negative output terminal of the power supply and the vertical input of the scope and the grounded scope case. Any ground current circulating in this loop as a result of the difference in potential EG between the two ground points causes an IR drop which is in series with the scope input. This IR drop, normally having a 60 Hz line frequency fundamental, plus any pickup on the unshielded leads interconnecting the power supply and scope, appears on the face of the CRT. The magnitude of this resulting noise signal can easily be much greater than the true ripple developed between the plus and minus output terminals. of the power supply, and can completely invalidate the measurement.

5-23 The same ground current and pickup problems can exist if an RMS voltmeter is substituted in place of the oscilloscope in Figure 5-3. However, the oscilloscope display, unlike the true RMS meter reading, tells the observer immediately whether the fundamental period of the signal displayed is 8.3 milliseconds (1/120 Hz) or 16, 7 milliseconds (1/60 Hz). Since the fundamental ripple frequency present on the output of an HP supply is 120 Hz (due to full-wave rectification), an oscilloscope display showing a 120 Hz fundamental component is indicative of a "clean" measurement setup, while the presence of a 60 Hz fundamental usually means that an improved setup will result in a more accurate (and lower) value of measure ripple.

5-24 Figure 5-3 shows a correct method of measuring the output ripple of a constant voltage power supply using a single-ended scope. The ground loop path is broken by floating the power supply. Note that to ensure that no potential difference exists between the supply and the oscilloscope it is recommended that whenever possible they both be plugged into the same ac power buss. If the grounds must be at earth ground potential.

5-25 Either a twisted pair or (preferably) a shielded two-wire cable should be used to connect the output terminals of the power supply to the veritical input terminals of the scope. When using a twisted pair, care must be

taken that one of the two wires is connected to the grounded input terminal of the oscilloscope. When using shielded two-wire, it is essential for the shield to be connected to ground at one end only so that no ground current will flow through this shield, thus inducing a noise signal in the shielded leads.




Figure 5-3. Ripple and Noise, Test Setup

5-26 To verify that the oscilloscope is not displaying ripple that is induced in the leads or picked up from the grounds, the (+) scope lead should be shorted to the (-) scope lead at the power supply terminals. The ripple value obtained when the leads are shorted should be subtracted from the actual ripple measurement.

5-27 In most cases, the single-ended scope method of Figure 5-3 will be adequate to eliminate non-real components of ripple and noise so that a satisfactory measurement may be obtained. However, in more stubborn cases it may be necessary to use a differential scope with floating input as shown in Figure 5-3C. If desired, two single conductor shielded cables may be substituted in

place of the shicided two-wire cable with equal success. Because of its common mode rejection, a differential oscilloscope displays only the difference in signal between its two vertical input terminals, thus ignoring the effects of any common mode signal introduced because of the difference in the AC potential between the power supply case and scope case. Before using a differential input scope in this manner, however, it is imperative that the common mode rejection capability of the scope be verified by shorting together its two input leads at the power supply and observing the trace on the CRT. If this trace is a straight line, the scope is properly ignoring any common mode signal present. If this trace is not a straight line, then the scope is not rejecting the ground signal and must be realigned in accordance with the manufacturer's instructions until proper common mode rejection is attained.

5-28 To check the ripple and noise output, proceed as follows:

- a. Connect the oscilloscope or RMS voltmeter as shown in Figures 5-3B or 5-3C.
- Adjust VOLTAGE control until front panel meter indicates the maximum rated output voltage.
- The observed ripple and noise should be less than 200 μVrms and 1 mV p-p.
- 5-29 Noise Spike Measurement. When a high frequency spike measurement is being made, an instrument of sufficient bandwidth must be used; an oscilloscope with a bandwidth of 20 MHz or more is adequate. Measuring noise with an instrument that has insufficient bandwidth may conceal high frequency spikes detrimental to the load.
- 5-30 The test setups illustrated in Figures 5-3A and 5-3B are generally not aceptable for measuring spikes; a differential oscilloscope is necessary. Furthermore, the measurement concept of Figure 5-3C must be modified if accurate spike measurement is to be achieved:
  - As shown in Figure 5-4, two coax cables, must be substituted for the shielded twowire cable.
  - Impedance matching resistors must be included to eliminate standing waves and cable ringing, and the capacitors must be connected to block the DC current path.
  - c. The length of the test leads outside the coax is critical and must be kept as short as possible; the blocking capacitor and the impedance matching resistor should be connected directly from the inner conductor of the cable to the power supply terminals.
  - d. Notice that the shields of the power supply

- end of the two coax cables are not connected to the power supply ground, since such a connection would give rise to a ground current path through the coax shield, resulting in an erroneous measurement,
- The measured noise spike values must be doubled since the impedance matching resistors constitute a 2-to-1 attenuator.
- f. The noise spikes observed on the oscilloscope should be less than 0.5 mV p-p.




Figure 5-4. CV Noise Spike Test Setup

5-31 The circuit of Figure 5-4 can also be used for the normal measurement of low frequency ripple and noise; simply remove the four terminating resistors and the blocking capacitors and substitute a higher gain vertical plug-in in place of the wideband plug-in required for spike measurements. Notice that with these changes, Figure 5-4 becomes a two-cable version of Figure 5-3C.

#### 5-32 Transient Recover Time.

Definition: The time "X" for output voltage recovery to within "Y" millivolts of the nominal output voltage following a "Z" amp step change in load current – where: "Y" is specified separately for each modal but is generally of the same order as the load regulation specification. The nominal output voltage is defined as the DC level half way between the static output voltage before and after the imposed load change, and "Z" is the specified load current change, normally equal to the full load current rating of the supply.

- 5-33 Transient recovery time may be measured at any input line voltage combined with any output voltage and load current within rating.
- 5-34 Reasonable care must be taken in switching the load resistance on and off. A hand-operated switch inseries with the load is not adequeate, since the resulting

one-shot displays are difficult to observe on most oscilloscopes, and the arc energy occurring during switching action completely macks the display with a noise burst. Transistor load switching devices are expensive if reasonably rapid load current changes are to be achieved.




Figure 5-5. Transient Recovery Time, Test Setup

- 5-35 A mercury-wetted relay, as connected in the load switching circuit of Figure 5-5 should be used for loading and unloading the supply. When the load switch is connected to a 60 Hz AC input, the mercury-wetted relay will open and close 60 times per second. Adjustment of the 25 k control permits adjustment of the duty cycle of the load current switching and reduction in jitter of the oscilloscope display.
- 5-36 The maximum load ratings listed in Figure 5-5 must be observed in order to preserve the mercury-wetted relay contacts. Switching of larger load currents can be accomplished with mercury pool relays; with this technique fast rise times can still be obtained, but the large inertia of mercury pool relays limits the maximum repetition rate of load switching and makes the clear display of the transient recovery characteristic on an oscilloscope more difficult.
- 5-37 To check the transient recovery time, proceed as follows:
  - a. Connect test setup shown in Figure 5-5.
  - b. Set METER SELECTION switch to mA.

- Turn on supply and adjust voltage controls until front panel meter indicates exactly the maximum rated output current.
- Close the line switch on the repetitive load switch setup.
- e. Set the oscilloscope for internal sync and lock on either the positive or negative load transient spike.
- f. Set the vertical input of the cilloscope for ac coupling so that small do level changes in the output voltage of the power supply will not cause the display to shift.
- g. Adjust the vertical centering on the scope so that the tail ends of the no load and full load waveforms are symetrically displaced about the horizontal center line of the oscilloscope. This center line now represents the nominal output voltage define in the specification.
- Adjust the horizontal positioning control so that the trace starts at a point coincident with a major graticule division. This point is then representative of time zero.
- Increase the sweep rate so that a single transient spike can be examined in detail.
- j. Adjust the sync controls separately for the positive and negative going transients so that not only the recovery waveshape but also as much as possible of the rise time of the transient is displayed.
- k. Starting from the major graticule division representative of time zero, count to the right 50 μsec and vertically 15 mV. Recovery should be within these tolerances as illustrated in Figure 5-6.




Figure 5-6. Transient Recovery Time, Waveforms.

#### 5-38 Output Stability

Definition: The change in output voltage for the first eight hours following a 30 minute warm-up period. Dur-

ing the interval of measurement all parameters, such as load resistance, ambient temperature, and input line voltage are held constant.

This measurement is made by monitoring the output of the power supply on a differential voltmeter or digital voltmeter over the stated measurement interval: strip chart recorder can be used to provide a permanent record. A thermometer should be placed near the supply to verify that the ambient temperature remains constant during the period of measurement. The supply should be put in a location immune from stray air currents topen doors or windows, air conditioning vents': if possible, the supply should be placed in an over writch is held at a constant temperature. Care must be taken that the measuring instrument has a stability over the eight hour interval which is at least an order of magnitude better than the stability specification of the power supply being measured. Typically, a supply may drift less over the eight hour measurement interval than during the 1/2 hour warm-up period.

5-40 To check the output stability, proceed as follows:

- Connect the load resistance and differential voltmeter as illustrated in Figure 5-2.
- Adjust front panel VOLTAGE controls until the differential voltmeter indicates the following:

6212B	100 V
6214B	10 V
6216B	25 V
6218B	50 V

- c. Allow 30 minutes warm-up then record the differential voltmeter
- After 8 hours, differential voltmeter should change from indication recorded in step c by less then the following:

6212B	105 mV
6214B	15 mV
6216B	30 mV
6218B	55 mV

#### 5-41 Constant Current Tests

5-42 For output current measurements, the current sampling resistor must be treated as a four terminal device. In the manner of a meter shunt, the load curent is fed to the extremes of the wire leading to the resistor while the sampling terminals are located as close as possible to the resistance portion itself (see Figure 5-7). Generally, any current sampling resistor should be of the low noise, low temperature coefficient (less than 30

ppm/°C) type and should be used at no more than 5° of its rated power so that its temperature rise will minimized. The latter, reduces resistance changes dur to thermal fluctuations. It is recommended that for resistor R<sub>S</sub> the user obtain a duplicate of the sampling resistance (R33) that is used in this unit for constant current checks. For these tests, then, R<sub>L</sub> is the difference between full-load resistance and current sampling resistor R<sub>S</sub>.




Figure 5-7. Current Sampling Resistor Connections.

#### 6-43 Rated Output and Meter Accuracy

- a. Connect test setup shown in Figure 5-8.
- b. Set METER SELECTION switch to mA position.
- c. Turn CURRENT controls fully clockwise.
- Turn on supply and adjust VOLTAGE controls until front panel meter indicates maximum rated output current.
- e. Voltmeter should read:




Figure 5-8. Constant Current, Test Setup

#### 5-44 Load Regulation:

Definition: The change, lour in the static value of the dc output current resulting from a change in load resistance from short circuit to a value which yellds maximum rated output voltage.

5-45 To check the constant current load regulation, proceed as follows:

- a. Connect test setup shown in Figure 5-8.
- h. Turn VOLTAGE control(s) fully clockwise.
- c. Set METER switch to mA.
- Adjust CURRENT control until front panel meter reads exactly the maximum rated output current.
- e. Read and record voltage indicated on voltmeter.
- f. Short out load resistor (R1).
- g. Reading on differential voltmeter should not vary from reading recorded in step e by more than the following:

Model No.	6212B	6214B	6216B	6218B
Variation (mVdc)	5.0	.05	1.5	3

#### 5-46 Line Regulation.

Definition: The change, IOUT in the static value of dc output current resulting from a change in ac input voltage over the specified range from low line (usually 103 Volts) to high line (usually 127 Volts), or from high line to low line.

#### 5-47 To check the line regulation proceed as follows:

- a. Utilize test setup shown in Figure 5-8.
- Connect variable auto transformer between input power source and power supply power input.
- c. Adjust auto transformer for 103 Vac input.
- d. Turn VOLTAGE control(s) fully clockwise.
- e. Set METER switch to mA.
- f. Adjust CURRENT controls until front panel meter reads exactly the maximum rated output current.
- Read and reccord voltage indicated on voltmeter.
- h. Adjust variable auto transformer for 127 Vac input.
- Reading on voltmeter should not vary from reading recorded in step g by more than the following:

Model No. 6212B 6214B 6216B 6218B Variation (mVdc) 5.0 0.75 1.5 3.0

#### 5-48 Ripple and Noise

Definition: The residual ac current which is superimposed on the do output current of a regulated supply. Ripple and noise may be specified and measured in terms of its RMS or (preferably) peak-to-peak value.

5-49 Most of the instructions pertaining to the ground loop and pickup problems associated with constant voltage ripple and noise measurement also apply to the measurement of constant current ripple and noise. Figure 5-9 illustrates the most important precautions to be observed when measuring the ripple and noise of a constant current supply. The presence of a 120 cycle waveform on the oscilloscope is normally indicative of a correct measurement method. A waveshape having 60 Hz as its fundamental component is typically associated with an incorrect measurement setup.

5-50 Ripple and Noise Measurement. To check the peak-to-peak ripple and noise, proceed as follows:

- Connect the oscilloscope as shown in Figures 5-9B or 5-9C.
- b. Rotate the VOLTAGE control fully cw.
- c. Set METER switch to mA and turn on supply.
- Adjust CURRENT control until front panel meter reads exactly the maximum rated output current.
- e. The peak-to-peak ripple and noise indication should be less than:

6212B	6214B	6216B	6218B
5.0 mV	0.5 mV	1.5 mV	3.0 mV

#### 5-51 TROUBLESHOOTING

5-52 Before attempting to troubleshoot this instrument, ensure that the fault is with the instrument and not with an associated circuit. The performance test (Paragraph 5-8) enables this to be determined without having to remove the instrument from the cabinet.

#### NOTE

The normal voltages shown on the schematic diagram at the rear of the manual are positioned adjacent of the applicable test point (identified by encircled numbers on the component location diagram and schematic diagram, Figures 7-1 and 7-2).




Figure 5-9. CC Ripple and Noise Test Setup

5-53 A good understanding of the principles of operation is a helpful aid in troubleshcoting, and it is recommended that the read review Section IV of the manual before attempting to troubleshoot the unit in detail. Once the principles of operation are understood, refer to the overall troubleshooting procedures in Paragraph 5-56 to locate the symptom and probable cause.

5-54 Once the defective component has been located (by means of visual inspection or trouble analysis) replace it and reconduct the performance test. If a component is replaced, refer to the repair and replacement and adjustment and calibration paragraphs in this section.

#### 5-55 Overall Troubleshooting Procedure

5-56 To locate the cause of trouble follow steps 1, 2, and 3 in sequence.

- Check for abvious troubles such as open fuse, defective power cord, input power failure, or defective voltage or current meter. Next remove the top and bottom covers, as described in Paragrpah 5-3, and inspect for open connections, charred components, etc. If the trouble source cannot be detected by visual inspection, proceed with step 2.
- In almost all cases, the trouble can be caused by the dc bias or reference voltages; thus, it is a good practice to check voltages in Table 5-2 before proceeding with step 3.
- 3. Examine Table 5-3 to determine your symptom, then check the probable cause.

5-57 Regulating Loop Troubles. If the voltages in Table 5-2 have been checked to eliminate the reference, blas and rectifier circults as a source of trouble the malfunction is caused by the voltage regulating loop. If any component in a feedback loop is defective, measurements made anywhere in the loop may appear abnormal. Under these circumstances it is very difficult to separate cause from effect with the loop closed. As described in Tables 5-4 and 5-5, the loop is effectively opened by checking the conduction and cutoff capability of each stage as follows:

- Shorting the emitter to collector of a transistor simulates saturation, or the full ON condition.
- Shorting the emitter to base or opening the collector lead of a transistor cuts it off, and simulates an open circuit between emitter and collector.

5-58 For low or high output voltage perform the instructions in Tables 5-4, or 5-5, respectively. Although a logical first choice might be to start near the loop midpoint, and then perform successive subdividing test, it is more useful to trace the loop from the series regulator backwards a stage at a time, since loop failures occur more often at the higher power levels.

Table 5-2. Reference, Blas, and Filtered DC Troubleshooting

METER COMMON	METER POSITIVE	NORMAL VDC	NORMAL RIPPLE (P-P)	PROBABLE CAUSE
C5 (-)	C5 (+)	+40 ± 4.8 V	2 <sub>,</sub> V	T1,C10,CR10,CR11,C5
+5	7	+11.5 ± 0.6 V	0.5 mV	VR4, VR5, VR6, Q11, R25
+\$	8	+6.2 ± 0.3 V	0.2 m\/	VR6, R25
9	+\$	+6.2 ± 0.3 V	0.1 mV	VR3, VR8, Q9, R30
11:	+S	+ 12.4 ± 0.6 V	4.5 mV	VR1, VR9, R30, R20(6212)
- OUT	6	150 ± 15.0 V (6212B)  19 ± 2.2V (6214B)  44 ± 4.5 V (6216B)	500 mV 500 mV 400 mV	6212B CR15-CR18, C9, R32, T1, C11 6214B CR15-CR18, C9, R32, T1, C11
*		78 ± 7.8 V (6218B)	400 mV	6216B CR15, CR16, C9, C11, C12, R32, T1 6218B CR15, CR16, C9, C11, C12, R32, T1

Table 5-3. Overall Troubleshooting

SYMPTOM	PROBABLE CAUSE
Lpw Output Cr.No Out- put Voltage	Ensure that the front panel meter is not defective, then refer to paragraph 5-58.
High Out- out Voltage	Ensure that the front panel meter is not defective, then refer to paragraph 5-58.
	e output voltage controls to zero
	here is nigh or low output voltage he voltage controls could result

SYMPTOM	PROBABLE CAUSE		
Inability To Reach 0V ± 1 mV Output	<ul><li>a. Output voltage control R10 defective.</li><li>b. Amplifier Q1, Q2 defective.</li></ul>		
Oscillates	C3, R17 defective		
Slow Drift	a. Measuring equipment b. Reference diode VR6 c. Q1 or Q2 d. Insufficient warm-up time (should be 30 minutes).		

Table 5-3. Overall Troubleshooting (Continued)

SYMPTOM	PROBABLE CAUSE
High Ripple	<ul> <li>a. Check operating setup for ground loops.</li> <li>b. If output floating, connect 1 μf capacitor between output and ground.</li> <li>c. Check for excessive internal ripple; refer to (Table 5-2).</li> <li>d. Ensure that supply is not in constant current mode under loaded conditions.</li> <li>e. Check that the test point (15) is approx0.5 V. If voltage is between 0 and +3 V, supply is in constant current operation or constant current input amplifier is defective.</li> </ul>
Poor Tran- sient Re- covery Time	R17, C3 defective Recovery Time
Poor Line Regulation (Constant Voltage)	<ul> <li>a. Improper measuring technique; refer to paragraph 5-11.</li> <li>b. Check reference circuit voltages, (Table 5-2).</li> </ul>
Poor Load Regulation (Constant Voltage)	a. Improper measuring technique; refer to paragraph 5-11. b. Check reference circuit voltage (Table 5-2).
Poor load Regulation (Constant Voltage) (Cont'd)	c. Ensure that supply is not in constant current operation under loaded conditions. To prevent this condition, ensure that output current does not exceed maximum rated output and that the current controls are fully clockwise.

SYMPTOM	PROBABLE CAUSE
Poor Stability (Constant Cyrrent)	<ul> <li>B. Check -6.2 Vdc reference voltage (Table 5-2).</li> <li>b. noisy programming resistor R11.</li> <li>c. CR20, CR14, C14 leaky.</li> <li>d. Check R42, R48, and R33 for noise or drift.</li> <li>e. Stage Q12/Q13 defective.</li> </ul>
Poor Stability (Constant Voltage)	<ul> <li>a. Check +6.2 Vdc reference voltage (Table 5-2).</li> <li>b. Noisy programming resistor P10.</li> <li>c. CR1, CR2 leaky.</li> <li>d. Check R1, R12, and C1 for noise or drift.</li> <li>e. Stage Q1/Q2 defective.</li> </ul>
Poor Load Regulation (Constant Current)	<ul> <li>a. Improper measuring technique; refer to paragraph 5-43.</li> <li>b. Check reference circuit voltages (Table 5-2).</li> <li>c. C14 and CR14 leaky.</li> <li>d. Check clamp circuit C3, CR3, CR4, and VR2.</li> <li>e. Ensure that supply is not crossing over into constant voltage operation. To prevent this condition, load the supply and turn the VOLTAGE control fully clockwise.</li> </ul>

	Table 5-4. Lovy Out	put Voltage Troubleshootin	9
STEP	ACTION	RESPONSE	PROBABLE CAUSE
1	Turn the VOLTAGE control fully clockwise and disconnect the load		
2	To eliminate the constant current circuit as a cause of the malfunction, remove CR6 cathode or anode lead	a. Output increases b. Output remains low	a. CR6 or constant current amplifier defective b. Reconnect CR6 and proceed to Step 3
3	Check conduction of Q7 by short- ing Q5 emitter to collector.	a. Output remains low     b. Output increases	a: Q7, CR7 or associated parts defective. b. Remove jumper and proceed to Step 4.
4	Check conduction of Q5 by short- ing Q4 emitter to collector	a. Output remains low b. Output increases	a. Q5, CR13, R19, R23 b. Remove jumper and proceed to Step 5.
5	Check conduction of Q4 by short- ing Q1 emitter to collector	a. Output remains low b. Output increases	a. Stage Q4 defective b. Stage Q1/Q2 defective Check R10, C1 for short and R12 for open.

Table 5-5. High Output Voltage Troubleshooting

STEP	ACTION	RESPONSE	PROBABLE CAUSE
1	Turn the VOLTAGE control to approximately mid-range and disconnect the load. If the output voltage should rise to an excessive value during the following procedures, the VOLTAGE control could be damaged if it is turned full CCW.		
2	Check turnoff of Q7 by disconnecting Q5 emitter lead	a. Output remains high     b. Output decreases	a. Q7, CR7 or associated parts defective. b. Replace Q5 and proceed to Step 3.
3	Check turnoff, of Q5 by removing Q4 collector lead	Output remains high     Output decreases	a. Stage Q5 defective b. Replace Q4 collector lead and proceed to Step 4.

Table 5-5. High Output Voltage Troubleshooting (continued)

STEP	ACTION	HESPONSE	PROBABLE CAUSE
4	Check turnoff of Q4 by removing Q1 collector lead	a. Output remains high b. Output decreases	a. Stage Q4 defective b. Replace Q1 collector lead and proceed to Step 5.
5	Remove CR3 anode or cathode	a. Output decreases b. Output remains high	a. voltage clamp circuit is defective b. Reconnect CR3 and proceed to Step 6.
( <b>S</b>	Connect a jumper between ( – ) out and test point (1)	a. Output remains high b. Output decreases	a. Stage Q1/Q2 defective b. Remove short and check R10 for open and R12 for short

#### Table 5-6. Selected Semiconductor Characteristics

REFERENCE DESIGNATOR	CHARACTERISTICS	HP PART I	SUGGESTED REPLACEMENT
07	Power NPN Silicon h <sub>fe</sub> = 35 min. @IC = 4A VCE = 4 V	1854-0225	2N3055 R.C.A.

#### 5-59 REPAIR AND REPLACEMENT

5-60 Before servicing a printed wiring board, refer to Figure 5-10. Section VI of this manual contains a tabular list of the instrument's replaceable parts. Before replacing a semiconductor device, refer to Table 5-6 which lists the special characteristics of selected semiconductors. If the device to be replaced is not listed in Table 5-6, the standard manufacturers' part number listed in Section VI is applicable.

## 5-61 ADJUSTMENT AND CALIBRATION

5-62 Adjustment and calibration may be required after performance testing, troubleshooting, or repair and replacement. Perform only those adjustments that affect the operation of the faulty circuit and no others.

#### 5-63 Meter Mechanical Zero

5-64 Proceed as follows to zero meter:

- a. Turn off instrument (after it has reached normal operating temperature) and allow 30 seconds for all capacitors to discharge.
- b. Insert sharp pointed object (pen point or

awl) into the small hole at top of round black plastic disc located directly below meter face.

c. Rotate plastic disc clockwise (cw/ until meter reads zero, then rotate ccw slightly in order to free adjustment screw from meter suspension. If point moves, repeat steps b and c.


#### 5-65 Meter Calibration

5-66 To calibrate the ammeter, proceed as follows:

- a. Connect test sotup shown on figure 5-8.
- b. Set CURRENT control fully clockwise.
- c. Set METER SELECTION switch to mA.
- Turn on supply and adjust VOLTAGE controls so that differential voltmeter indicates exactly as follows:

6212B 1.00 V 6216B 1.15 V 6214B 1.00 V 6218B 1.20 V

e. Adjust R52 until front panel ammeter indicates: 6212B, 100 mA; 6214B, 1 A; 6216B, 400 mA; 6218 B, 200 mA.



#### Section VI REPLACEABLE PARTS

#### 6-1 INTRODUCTION

- 6-2 This section contains information for ordering replacement parts. Table 6-4 lists parts in alphanumeric order by reference designators and provides the following information:
  - a. Reference Dasignators. Refer to Table 6-1.
- b. Description. Refer to Table 6-2 for abbreviations.
  - c. Total Quantity (TQ). Given only the first time the part number is listed except in instruments containing many sub-modular assemblies, in which cace the TQ appears the first time the part number is listed in each assembly.
  - d. Manufacturer's Part Number of Type.
  - e. Manufacturer's Federal Supply Code Number. Refer to Table 6-3 for manufacturer's name and address.
  - f. Hewlett-Packard Part Number:
  - g. Recommended Spare Parts Quantity (RS) for complete maintenance of one instrument during one year of isolated service.
  - h, Parts not identified by a referency designator are listed at the end of Table 6-4 under Mechanical and/or Miscellaneous. The former consists of parts belonging to and grouped by individual assemblies; the latter consists of air parts not immediately associated with an assembly.

#### 6-3 ORDERING INFORMATION

6-4 To order replacement parts, address order or inquiry to your local Hewlett-Packard sales office (see lists at rear of this manual for addresses). Specify the following information for each part: Model, complete serial number, and any Option or special modification (J) numbers of the instrument; Hewlett-Packard part number; circuit reference designator; and description. To order a part not listed in Table 6-4, give a complete description of the part, its function, and its location.

Table 6-1. Reference Designators.

A C CB CR DS	= assembly = blower (fan) = capacitor = circuit breaker = diode = device, signaling (lamp)	E :JKLM	= miscellaneous electronic part = fuse = jack, jumper = relay = inductor = meter

Table 6-1. Reference Designators (Continued)

P Q	= plug = transistor	٧	= varuum tubo, neon bulb,
R S	= resistor = switch	VR	photocell, etc.
TB TS	= transformer = terminal block = thermal switch	×	<ul><li>socket</li><li>integrated circuit or network</li></ul>
2	= trieffilai switch	<u> </u>	cult of Herwork

Table 6-2, Description Abbreviations

A ·	= ampere	mod.	= modular or
ac .	= alternating		modified
ł	current	ımtg	= mounting
assy.	= assembly	n	= nanc = 10-9
bd	= board	NC	= nc mally closed
bkt	= bracket	NO	= normally open
°C	= degree	NP	= nickel-plated
	Centigrade	U	= elim
cd	= card	opd	= order by
coef	= coefficient	l	description
	= composition	OD	= outside
CRT	= cathode-ray		diemeter
l _	tube	p	= pico = 10 - 12
	= center-tapped	P.C.	= printed circuit
dç	= direct current	pot.	= potentiometer
DPDT	= double pole,	р-р	= peak-to-peak
	double throw	ppm	= parts per
elect	= electrolytic		million
	= encapsulated	pvr	= peak reverse
F	= farad	l	voltage
	= degree Farenheit	rect	= rectifier
fxd	= fixed	rms	= root mean
Ge	≔ germanium	1	square
H	= Henry	Si	= silicon
Hz	= Hertz	SPDT	• , ,
IC	= integrated circuit		single throw
ID	= inside diameter	SS	= small signal
incnd	= incandescent	T	= slow-blow
k	= kilo = 103	tan.	= tantulum
m M	= milli = 10-3 = mega = 106	Ti	= titanium
	= mega = 100 = micro = 10-6	V.	= volt
μ met.	= micro = 10=0	var	= variable
met. mfr	= metal = manufacturer	ww	
11111	= manulacturer	W	= Watt
	100		
	ŀ	ĺ	•

Table 6-3. Hanufacturer's Federal Supply Codes

01121	Allen-Bradley Co.	Hilwaukee, WI
03508	General Electric Co.	Auburn, NY
04713	Hotorola Samiconductor Producta, Inc.	Phoenix, AZ
06001	Hepco/Electra Corp.	Columbus, SC
14140	Edison Elek Division McGraw-Edison	Henchester, NH
19701	Hepco/Electra Corp.	Mineral Wells, TX
24546	Corning Class Works	Bradford, PA
28480	Hewlett-Packard Co.	Palo Alto, CA
56289	Sprague Electric Co.	North Adams, MA

Table 6-4. 621B/14B/16B/18B/ Parts List

	· T				
Ref Desig	HP Part No	aty	Description	Hfr Code	Hfr Part No
C1 C2 C3 6212B 6214B 6216B 6218B C4 6212B 6214B 6216B	0180-1835 0160-0157 0160-0159 0160-0157 0160-2061 0160-0157 0160-0157	1 1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Al MAIN BOARD  NOT ASSIGNED  fxd elect 68uF ±20% 15V  fxd film 4700pF ±10% 200V  fxd film 6800pF ±10% 200V  fxd film 4700pF ±10% 200V  fxd film 4700pF ±10% 200V  fxd cer 100pF ±10% 200V  fxd film 4700pF ±10% 200V  fxd film 4700pF ±10% 200V  fxd film 4700pF ±10% 200V	56289 28480 28480 28480 28480 28480	150D686X0015R2
6218B C5 6212B 6214B 6216B 6218B C6	0160-0157 0160-1852 0180-1884 0180-1852 0180-1852 0160-0161	1 1 1 1 1	fxd film 4700pf ±10% 200V	28480 28480 28480 28480 28480 28480	
6212B 6214B 6216B 6218B C8 C9 6212B	0160-3070 0160-3070 0160-3070	1	NOT ASSIGNED fxd mice 100pF +5% 300V fxd mice 100pF +5% 300V fxd mice 100pF +5% 300V NOT USED fxd elect 200uF +75-10% 250V	28480 28480 28480	
6214B 6216B 6218B C10 6212B	0180-1916 0180-1888 0180-1887 0150-0024	1 1 1	fxd elect 2000uF+100-10% 28V fxd elect 490uF +75-10% 85V fxd elect 400uF +65-10% 150V fxd cer .02uF +80-20% 600V	28480 28480 06001 28480 28480	B7F655BAB
6214B 6216B 6218B C11	0150-0024 0150-0024 0150-0024 0150-0024	2 3 2	fxd cer .02uF +80-20% 600V fxd cer .02uF +80-20% 600V fxd cer .02uF +80-20% 600V	28480 28480 28480	

Table 6-4. 6218/148/168/188/ Parts List (cont.)

Ref Desig	HP Part No	Qty	Description	Mfr Code	Mfr Part No
C12	. : .				
6212B	1	1	NOT ASSIGNED	ľ	
6214B	<b>i</b> .		NOT ASSIGNED		·
6216B	0150-0024	Į.	fxd cer .02uF +80-20% 600V	28480	Į.
6218B		1	NOT ASSIGNED		
C13	:	ľ	NOT USED	İ	
C14 1	1			ľ	
62128	0180-1851	1 1	fxd elect 80uF +75-10% 300V	06001	87F742BA4
6214B	0180-2258	Ιï	fxd elect BOUf +50-10% 65V	28480	
6216B	0180-2258	Ιĩ	fxd elect 80uF +50-10% 65V	28480	
6218B	0180-2258	l i	fxd elect 80uF +50-10% 65V	28480	}
C15	0150-2170	1 .	180 01000 0001 7511-108 051	20700	1
6212B		1	NOT ASSIGNED		
6212B	0180-2141	lı	fud alast 3 July 108 500	56289	150D335X9050B2
		ł i l	fxd elect 3.3uF ±10% 50V fxd elect 3.3uF ±10% 50V	56289	
62168	0180-2141	1	TXD elect 3.3ur +10% 30V		150D335X9050B2
6218B	0180-1836	l. 1	fxd elect 5uF +75-10% 65V	28480	<b>.</b>
0.4.70	'	l i	NOT HEED	ŀ	1.
C16-30	: ,		NOT USED	1	
C31		1 ,	<b>.</b>	l <sup>.</sup>	
6212B	0160-0174	1 1	fxd cer 0.47uF +80-20% 25V	I	
6214B		1 1	NOT ASSIGNED		
6216B			NOT ASSIGNED		ł
6218B		i 1	NOT ASSIGNED		•
CR1,2	1901-0033	4	gen prp 200mA 180V	28480	•
CR3	1901-0461	3	gen prp 10V 200mA	28480	
CR4	1901-0033		gen prp 200mA 180V	28480	
CR5,6	1001 011	1			
CR7	2701 0101		·		
1 6212B	1901-0328	6	pwr rect 1A 400V	03508	A14D
6214B	1901-0327	l ĕ l	pwr rect 1A 200V	03508	A148
6216B	1901-0327	6	owr rect 1A 200V	03508	A14B
6218B	1901-0327	8			A14B
	1901-0527	°'	pwr rect 1A 200V	03508	A14B
CR8,9		l i	NOT USED		
CR10,11	1001 0107	/ <u>,</u>			4340
1 6212B	1901-0327	2	pwr rect 1A 200V	U3508	A14B
6214B	1901-0327	1	pwr rect 1A 200V	03508	A14B
6216B	1901-0327		pwr rect 1A 200V	03508	A14B
6218B	1901-0327		pwr rect 1A 200V	0350B	A 14B
C012			NOT USED		
CR13	1901-0460	1 1	stabistor 150mA 30V	28480	l
CR14-16	1901-0327	1	pwr rect 1A 200V	03500	A148:
CR17,18			*		l .
6212B	1901-0327	[	pwr rect 1A 200V	03508	A14B
6214B	1901-0327		pwr rect 1A 200V	03508	A14B
6216E			NOT ASSIGNED		
6218B	1901-0327		pwr rect 1A 200V	03508	A148
CRIS		1	NOT USED		1
CR20	1901-0033	, [	gen prp 200mA 180V	28480	ľ
01,2			An heh enging tons	20700	
6212B	1854-0823	5	NPN SI	28480	
62148	1854-0823	4.	NPN SI	28480	
6216B	1854-0823	4	nan ai	28480	
62188		4	NPN SI NPN SI	28480	1
	1854-0823	. <b>"  </b>	INTIN DE	20400	
Q3,4	1051 0000	ا ي ا	PAP St i	20 4 2 2	
6212B	1853-0099	2	1.11. 31	28480	
6214B	1853-0099	3	PNP Si	28480	
6216B	1853-0099	3	PNP Si	28480	
6218B	1853-0099	3	PNP Si	28480	,
05	j	1	•		1
6212B	1854-0823	ĺĺ	NPN St	28480	1
6214B	1853-0041	1	PNP SI	28480	1
6216B	1853-0041	lil	PNP SI	28480	1
6218B	1853-0041	$\mathbf{i}$	PNP Si	28480	1
		* 1	•		t .

Table 6-4. 6218/148/168/188/ Parts List (cont.)

Ref Desig	HP Part No	Oty	Description	Mfr Code	Hfr Part No
46 47 48 49 410	1854-0087		NOT USED NOT ASSIGNED NOT HSED NOT USED NOT USED	28480	
62128 62148 6216B 6218B Q12,13	1853-0041 1853-0099 1853-0099 1853-0099 1854-0823		PNP SI PNP SI PNP SI PNP SI NPN SI	28480 28480 28480 28480	
6212B 6214B 6216B 6218B R2	0812-0050 0813-0001 0813-0001 0813-0001	1 1 2 1	Fxd, ww 3k 5% 5W Fxd, ww 1k 5% 3W Fxd ww 1k 5% 3W Fxd ww 1k 5% 3W	28480 28480 28480 28480	
6212B 6214B 6216B 6218B R3-5 R6	0757-0480	1	Fxd film 432k 1% 1/BW NOT ASSIGNED NOT ASSIGNED NOT ASSIGNED NOT USED	19701	MF4C1/8-T0-4323F
6212B 6214B 6216B 6218B R7 R8 R9	0737-0437 0757-0427 0757-0427 0757-0427	1 2 2 2	Fxd film 4.75k 1% 1/8W Fxd film 1.5k 1% 1/8W Fxd film 1.5k 1% 1/8W Fxd film 1.5k 1% 1/8W NOT USED NOT MASSIGNED NOT USED NOT ASSIGNED	24546 24546 24546 24546	C4-1/8-T0-4751-F C4-1/8-T0-1501-F C4-1/8-T0-1501-F C4-1/8-T0-1501-F
R11 R12 6212B 6214B 6216B 6218B R13 R14	0811-2573 0811-1808 0813-0001 0811-2879	1	FXd WH 1.124k 0.1% 1/8W FXd WH 2.6k 5% 3W FXd WH 1k 5% 3W FXd WH 4.64k 0.1% 1/5W NOT USED NOT ASSIGNED	14140 28480 28480 14140	1274-1/16-C-1124R 1350-1/16-E-46418
R15,16 R17 6212B 6214B 6216B 6218B R18	0636-1235 0686-6225 0686-7525 0686-6825	1 2 1 1	fxd comp 12k 5% 1/2W fxd comp 6.2k 5% 1/2W fxd comp 7.5k 5% 1/2W fxd comp 7.5k 5% 1/2W fxd comp 6.8k 5% 1/2W	01121 01121 01121 01121	EB1235 CB6225 EB7525 EB6825
6214B 6216B 6218B R19 6212B 6214B	0686-6225 0685-6225 0686-6225 0686-1035 0686-1025	1 1 2 2 2	fxd comp 20k 5% 1/2W fxd comp 6.2k 5% 1/2W fxd comp 6.2k 5% 1/2W fxd comp 6.2k 5% 1/2W fxd comp 10k 5% 1/2W fxd comp 1k 5% 1/2W	01121 01121 01121 01121 01121 01121	EB2035 EB6225 EB6225 EB6225 WB1035 EB1025
62168 62188 R20 62128 62148	0686-1025 0686-1025 0813-0010 0813-0010	3 3	fxd comp 1k 5% 1/2W fxd comp 1k 5% 1/2W fxd ww 820 5% 3W fxd ww 820 5% 3W	01121 01121 28480 28480	EB1025 EB1025
6216B 6218B	U764-0025 0764-0025	i	fxd met 2k 5% 2W fxd met 2k 5% 2W	28480 28480	

Table 6-4. 621B/14B/16B/18B/ Parts List (cont.)

Ref Desig	HP Part No	Qty	Description	Hfr Code	Hfr Part No
				0000	
R21 62128	0404 0015	l , l	5. 1 000 FF 1 (01)		
6214B	0686-2215 0686-2415	1	fxd camp 220 5% 1/2W fxd camp 240 5% 1/2W	01121	EB2215 EB2415
62168	0686-2415	i	fxd comp 240 5% 1/2W	01121	EB2415
6218B	0686-2215	Î	fyd comp 220 5% 1/2W	01121	EB2215
R22	5000-2217	•	1 x 0 0 0 mp 2 2 0 3 4 1 7 2 m	"""	102217
6212B	0686-5635	1	fxd comp 56k 5% 1/2W	01121	EB5635
62140	0686-3035	li	fxd comp 30k 5% 1/2W	01121	EB3035
6216B	0686-3035	1	fxd comp 30k 5% 1/2W	01121	EB3035
6218B	0686-3035	ı i	fxd comp 30k 5% 1/2W	01121	EB3035
, R23	1 1				
6212B	0683-1035	i '	fxd comp 10k 5% 1/4W	01121	CB1035
6214B	,		NOT ASSIGNED		
6216B			NOT ASSIGNED		
6218B	0400 7404	l , i	NOT ASSIGNED		
R24   R25	D689-3625	1	fxd comp 3.6k 5% 1W	01121	GB 3625
62128	0686-4315	1	fxd comp 430 5% 1/2W	1	CUAZIE
6214B	0686-4715	i	fxd comp 430 5% 1/2W	01121	EB4315 EB4715
6216B	0686-5115	i	fxd comp 510 5% 1/2W	01121	EB5115
62188	0686-4315	l i	fxd comp 430 5% 1/2W	01121	E84315
R26		-	7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	1	
62128	0686-1515	1	fxd comp 150 5% 1/2W	01121	EB1515
62148	0686-2015	li	fxd comp 200 5% 1/2W	01121	EB2015
6216B	0686-2015	i	fxd comp 200 5% 1/2W	01121	EB2015
6218B	0686-2015	1	fxd comp 200 5% 1/2W	01121	EB2015
, R27		1	NOT USED	,	
R20				1	
62128	0686-2025	1	fxd comp 2k 5% 1/2W	01121	EB2025
6214B	0686-8215	2	fxd comp 820 5% 1/2W	01121	EB8215
6216B	0686-8215	!	fxd comp 820 5% 1/2W	01121	E88215
6218B R29	0686-8215	1	fxd comp 820 5% 1/2W	01121	EBB215
R30	'		NOT USED	1	1
62128	0686-6815	lı	Exd comp 680 5% 1/2W	01121	EB6815
6214B	0686-3915	lil	fxd comp 390 5% 1/2W	01121	CB3215
62168	0686-1825	lil	fxd comp 1.8k 5% 1/2W	01121	EB1825
62188	0686-1825	lil	fxd comp 1.8k 5% 1/2W	01121	EB1825
R31		l '		"""	
6212B	0686-1025	2	fad comp 1k 5% 1/2W	01121	EB1025
62148	0686-0215		fad comp 820 5% 1/2W	01121	EB8215
62160	0686-1025	i	Exd comp 1k 5% 1/2W	01121	EB1025
62183	0686-1025		fxd comp 1k 5% 1/2W	01121	EB 1025
R 32		.			<u> </u>
62120	0764-9045	1 1	Ind mut 22k 5% 2W	28480	1
6214B	0311-1799	1	Fxd ww 370 5% 3W	28480	
62168	0698-3642	1 1	fxd met 3k 5% 2W	27167	FP42-2-100-1001-J
62183	OB11-1414	l l	fxd ww 6.5k 5% 3W	28480	[ ]
R 3 3					1
62128	0811-1718	1 1	fxd ww In 5% 3W	28480	
62148	0811-1340	1	fxd ww 1 5% 5W	28480	,
42168	0811-1986	}	fxd ww 3 0.5% 3N	28480	1
6218B	0811-2499	1	fad ww 6 0.5% 3W	28480	
R34,35			NOT USED	ì	I
62120	0686-1015	1	fud open 100 EM 1700	01101	Lennore
6212B			fxd comp 10C 5% 1/2W	01121	EB1015
6214B	1 L		NOT ASSIGNED NOT ASSIGNED	1	I .
6218B	*		NOT ASSIGNED	1	<b>I</b> '
R37,38			NOT USED	<b>F</b>	
			. to 🚰	1	
	1	1 1	14	I .	I

Table 6-4. 621B/14B/16B/18B/ Parts List (cont.)

	Table 6-4. 621B/14B/16B/18B/ Parts List (cont.)				
Ref Desig	HP Part No	QLy	Description	Mfr Code	Mfr Part 'o
R39 6212B 6214B 62168 6210B R40,41	0689-3335	1	Fxd comp 33k 5% 1W NUT ASSIGNED NOT ASSIGNED NUT ASSIGNED NOT USED	01121	GB3335
6212B 6214B 6216B 6218B R43	0698-3269 0698-3269 0698-5091 0698-5091	1 1 1	fxd film 23k 1% 1/8W fxd film 23k 1% 1/8W fxd film 45k 1% 1/8W fxd film 45k 1% 1/8W	24546 24546 24546 24546	C4-1/8-T0-2302-F C4-)/8-T0-2302-F C4-1/8-T0-4502-F C4-1/8-T0-4502-F
6212B 6214B 6216B 6218B R44-47	0757-0934 0757-0427 0757-0427 0757-0427	1	fxd film 2.7k 2% 1/8W fxd film 1.5k 1% 1/8W fxd film 1.5k 1% 1/8W fxd film 1.5k 1% 1/8W NOT USED	24546 24546 24546 24546	C4-1/8-T0-2701-G C4-1/8-T0-1501-F C4-1/8-T0-1501-F C4-1/8-T0-1501-F
R48 6212B 6214B 6216B 6218B R49,50 R51	0757-0280 0757-0280 0757-0280 0757-0280	1 2 2 1 1	fxd film lk 1% 1/8W fxd film lk 1% 1/8W fxd film lk 1% 1/8W fxd film lk 1% 1/8W	24546 24546 24546 24546	C4-1/8-T0-1001-F C4-1/8-T0-1001-F C4-1/8-T0-1001-F C4-1/8-T0-1001-F
62128 62148 62160 62165 R52	0757-0274	1	fxd film 1.21k 1% 1/8W NOT ASSIGNED NOT ASSIGNED NOT ASSIGNED	24546	C4-1/8-T0-1211-F
6212B 6214B 6216B 6218B R53-55 R56 R57 R58-60 R61	2100-0328 2100-0439 2100-0439 2100-0439	1 1 1	trmr ww 1-turn 500 10% trmr ww 1-turn 250 20% trmr ww 1-turn 250 20% trmr ww 1-turn 250 20% NOT ASSIGNED NOT USED NOT ASSIGNED NOT USED Fxd comp 1k 5% 1/2W	28480 28480 28480 28480	EB1025
VR1 VR2 VR3 VR4 VR5 VR6 VR7	1902-3185 1902-3070 1902-0761 1902-0064 1902-3070 1902-0761 1902-0049 1902-3070	1 3 2 1	zener 12.4V 5% zener 4.22V 5% zener 6.2V 5% zener 7.5V 5% zener 4.22V 5% zener 6.2V 5% zener 6.19V 5% zener 4.22V 5%	28480 28480 04713 28480 28480 04713 28480 28480	1N821 1N821
VR9 6212B 6214G 6216B 621BB Z1	1902-3002 1810-0031		zener 2.37 5% NOT ASSIGNED NOT ASSIGNED NOT ASSIGNED resistance network 14-dip multiple value	28480 28480	1
C1 6212B 6214B 6216B 6218B DS1	0180-1841 0180-0301 0180-1836 0180-1836 1450-0510	1 1 1 2	A2 FRONT PANEL BOARD  fxd elect 5uf +50-10% 150V fxd elect 5uF +75-10% 50V fxd elect 5uF +75-10% 65V fxd elect 5uF +75-10% 65V LED	56289 56289 28480 28480 28480	40D5051F150DC4 30D505G0508B2

Table 6-4. 621B/14B/16B/18B/ Parts List (cont.)

·	·	16 0-		List (con	(1)
Ref Desig	HP Part No	Qty	Description	Mfr Code	Mfr Part No
R1-7 R8			NOT ASSIGNED		
6212B 6214B	0686-7505 0686-2405	l 1	fxd comp 75 5% 1/2W fxd comp 24 5% 1/2W	01121	EB7505 EB2405
6216B	0686-2405	1	fxd comp 24 5% 1/2W	01121	EB2405
62188	0686-2405	1	fxd comp 24 5% 1/2W	01121	EB2405
R9	24	]	NOT ASSIGNED		]
71D 12120	2100-0998	1	ver dual ww 22k 10%	28480	
6214B	2100-2526	2	ver dual ww 5% 5%	28480	10
6216B	2100-2526	Ιī	var dual ww 5k 5%	28480	1
62'1B	2100-2527	2	var dual ww 10k 5%	28480	ļ
√ R 1 1					
62128	2100-2526	1	ver duel ww 5k 5%	28480	1
6214B 6216B	2100-2526 2100-2527	١,	ver duel ww 5% 5%	28480	
62188	2100-2527	1	ver duel ww 10k 5% ver duel ww 10k 5%	28480 28480	
R12,13	***************************************		NO) ASSIGNED	20480	
R14	'	'			
6212B	0698-5479	1	fxd comp 8-2 5% 1/2V	01121	E882G5
6214B	0686-0335	1,	fxd comp 3.3 5% 1/2W	01121	EB33G5
6216B	0686-0335	1	fxd comp 3.3 5% 1/2W	01121	EP 33G5
6218B ₹15-52	0686-0335	1	fxd comp 3.3 5% 1/2W	01121	Ta33G5
R53	. ,		NOT ASSEGNED		
62136	0757-0280	1	fxd film 1k 1% 1/8W	24546	C4-1/6-F0-1801-F
62148	0757-0280	i	fxd film lk 1% 1/80	24546	C4-1/8-10-1001-F
6216B	0757-0274	1:1	fxd film 1.21k 1% 1/8W	24,46	C4-1/8-TU-1211-F
621BB	11757-11274	1	fxd film 1.21k 1% 1/8W	24546	C4-1/8-10-1211-F
R54					
62128	0757-0467	1	fxd film 121k 1% 1/8W	24546	C4-1/8-T0-1213-F
62148	0698-5088	1	fxd film 12k 1% 1/8W	24546	C4-1/8-T0-1202-F
6216B	0698-5151	] ]	fxd film 29.9k 1% 1/8W	24546	C4-1/8-TU-2912-F
6218B R55	0698-3572	1 1	fxd film 60.4k 1% 1/8W	24546	C4-1/8-T0-6042-F
62128	0698-3440	l i l	fxd film 196 1% 1/8W	24546	C4-1/8-TU-196R-F
6214B	0698-3440	i i	fxd film 196 1% 1/8W	24546	C4-1/8-10-196R-F
6216B	0757-0269	Ţ	fxd film 270 1% 1/8W	24546	C4-1/8-70-271-F
62 .98	0757-0269	1	fxd film 270 1% 1/8W	24546	C4-1/8-T0-271-F
R56			NUT ASSIGNED		
837 62128	0757-0465	i	fxd film 100k 1% 1/8W	24545	CA 1/0 to 1007 5
62148	0698-6076	- i	fxd film 39k 1% 1/8W	24545 24546	C4-1/8-TU-1003-F C4-1/8-TO-3902-F
6216B	0698-5089	i l	fxd film 33k 1% 1/8W	24546	C4-1/8-10-3302-F
6218B	0698-5089	i	fxd film 33k 1% 1/8W	24546	C4-1/8-10-3302-F
51	3101-1258	1 ]	switch tgl 2A 250Vac	28480	
52	3101-1363	1	switch Bl 0.5A 125Vnc/dc	28480	
	· · ·		CHASSIS ELECTRICAL		
FL '	2110-0012	1	fuse 0.5 A, 250 V	28480	· ·
Q1-6		ı	NOT ASSIGNED		
07		_ [			
62128	1854-0421	1	NPN Si	28480	
6214B 6216B	1854-0225 1854-0225	1	NPN Si NPN Si	28480	· [
62188	1854-0239	1	NPN 51	28480 28480	
11	.0,4-0,,	•	DIT IT WE	20400	
62128	9100-2608	<b>1</b>	transformer	28480	
6214B	9100-2610	i	transformer	28480	
6216B	9100-2609	1	transformer	28480	
62188	9100-2609	1	transformer	28480	
<u> </u>					

Table 6-4. 621B/14B/16B/18B/ Parts List (cont.)

	I un	<u></u>		Luc	
Ref Desig	HP Part No	Qty	Description	lifr Code	Mfr Part No
	1412 110	╁╌			
		l	MECHANI CAL		
1			·	1	
6212B	06212-60020	1 1		28460	
6214B	06214-60020	1	P.C. Board Assembly, Main	28480	
6216B 6218B	06216-60021 06218-60021	1	(Includes Components)	28480	
02100		1		28480	
.:	0340-0168	2	Insulator Bushing (Q7) Insulator (Q7)	28480	
	0340-0174 1200-0181	l i	Insulator (Q5)	28480 28480	
	8120-0050	Ιi	Line Cord	28480	1
: <b>†</b>	0400-0013	Ĭ	Line Cord Strain Relief	28480	
<b>.</b>	2100-0564	1	Fuseholder Body	28480	
•	2100-0565	] ]	Fuseholder Cap	28480	
	2110-0569	1	Fuseholder Nut	28480	
	5020-2579 0370-0101	1 2	Heatsink Black Knob	28480 28480	
1	0370-0101	2	Red Knob	28480	:
1	1510-0094	2	Binding Post	28480	
	1510-0522	l ī	Binding Post	28480	
	7101-0748	1	Top Cover	28480	
1	7101-0749	1	Bottom Cover	28480	
1	5081-4968	1	Rear Cover with Lettering (115V)	28480	:
1	5081-4969	1	Rear Cover, 230V	28480	
	,,,,,	7	(Option £028)	20455	
		_	<u> </u>	<del></del>	
			Front Cover with Lettering	1	
6212B	06212-60004	1	•	28480	
6214B	06214-60004	1		28480	
6216B 6218B	06216-60004 06218-60004	1	·	28480 28480	
02100	00210-00004	<del>                                     </del>		20400	
		1	Front Penel Assembly		
6212B	06212-60002	1	1	28480	
6214B	06214 60002	1	•	28460	
6216B 6218B	06216-60002 06218-60002	1 1 1		28480 28480	
02100	00510-00005	1 1	Meters	20400	
6212B	1120-1247	1	2.25A, 120V	28480	
,6214B	1120-1133	1	2.25A, 12V	28480	
6216B	1120-1137	1	2.25A, 30V	28480	1
62188	1120-1142	1	2-254, 604	28480	'
	4040-0934 1460-0256	[ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	Meter Bezel Heter Spring	28480	1
1	5020-5757	1	Neter Spring Al Board (Blank)	28480 28480	
! !	5020-5731	i	A2 Board (Blank)	28480	1
<del>                                     </del>		<del>-</del>			
l ·			Al Board with Components	20480	
6212B	06212-60020	1		28480	
6214B 6216B	06214-60020 06216-60020	l l		28480 28480	
6210B	06218-60020	i	<i>i</i>	28480	
				71,17	
			A2 Board with Components		
6212B	06212-60021	1		28480	
6214B	06214-60021	l	1 · F	28480	
6216B 6218B	06216-60021 06218-60021	l l		28480 28480	
V.170	20214-00051	•		£1770U	
	5950-1928	l	Operating & Service Manual	28480	* ·
· [			· ·		
<u> </u>			1		

Jable 6-4, 6218/148/168/188/ Parts List (cont.

	<u> </u>					int.)
	Ref Desig	HP Part No	Qt	Description	Hfr Code	Hfr Part No
		9211-3319 9220-3212 9220-3213	1	Corrugated Container Corrugated Pad	28480 28480	
,e	R54		2	Foam Pad	28480	
	6212B 62J4B		1 1	fxd film 121k 1% 1/8W	24546	C4-1/8-T0-1213-F
•	6216B		li	fxd film 12k 1% 1/8W fxd film 29.9k 1% 1/8W	24546	C4-1/8-T0-1202-F
	62168	0698-3572	Ī	fxd film 60.4k 1% 1/8W	24546 24546	C4-1/8-10-2912-F
	R55 6212B	0698-3440	1 .		24346	C4-1/8-T0-6042-F
Ì	6214B	0698-3440	$\begin{bmatrix} 1 & 1 \\ 1 & 1 \end{bmatrix}$	fxd film 196 1% 1/8W fxd film 196 1% 1/8W	24546	C4-1/8-T0-196R-F
1	6216B	0757-0269	l î	fxd film 270 1% 1/8W	24546	C4-1/8-TO-196R-F
	6218B	0757-0269	Ī	fxd film 270 lw 1/RW	24546 24546	C4-1/8-T0-271-F
١	R56 R57		j .	NOT ASSIGNED	24,746	C4-1/8-T0-271-F
ı	6212B	0757-0465	1	fxd film 100k 1% 1/8W	1	i
1	6214B	0698-6076	: ī	fxd film 39k 1% 1/8W	24545	C4-1/8-T0-1003-F
ŀ	6216B	0698-5089	1	fxd film 33k 1% 1/8W	24546 24546	C4-1/8-70-3902-F
1	6218B 51	0698-5089	1	fxd film 33k l% 1/AW	24546	C4-1/8-T0-3302-F C4-1/8-T0-3302-F
	52	3101-1258 3101-1363	-1 1	switch tgl 2A 250Vac	28480	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
1	- <del>-</del>	1 3101-1505		switch sl 0.5A 125Vsc/dc	28480	
İ				CHASSIS ELECTRICAL	ł	l
	F1 F2	2110-0012	1	fuse 0.5 A. 250 v	28480	1
1	• 4	2110-0004	1	fuse 0.25 A. 250 V (for upo	19700	<b>.</b>
ŀ	Q1-6		,	in Option 028 units only) NOT ASSIGNED	]	
1	Q7	2			}	
L	6212B 6214B	1854-0421 1854-0225	1	NPN SI	28480	1
I	6216B	1854-0225	1	NPN Si NPN Si	28480	· .
	62188	1854-0239	î	NPN SI	28480	· ·
Г	T1	}	_	)	28480	
1	6212B	9100-2608 9100-2610	1	transformer	28480	
ı	6216B	9100-2609	1 1	transformer	28480	
	6218B	9100-2609	i	transformer transformer	28480	
H	Sal es es			cranstormer	28480	
				HECHANICAL PARTS		
		0340-0168	2	Insulator Bushing (Q7)	28480	
ļ.		0340-0174 1200-0181	1 }	Insulator (07)	28480	j"
L		8120-0050	1	Insulator (Q5) Line Cord	28480	
		0400-0013		Line Cord Strain Relief	28480	• [
	· i	2100-0564		Fuseholder Body	28480 28480	ļ
	. ,	2100-0565	1	Fuseholder Cap	28480	
l	ľ	2110-0569 5020-2579	1	Fuseholder Nut	28480	
		0370-0101	1 2	Heatsink Black Knob	28480	
		0370-2241		Red Knob	28480	
	100	1510-0094	2	Binding Post	28480 28480	
		1510-0522	1	Binding Post	28480	
		7101-0740	1	Top Cover	28480	
٠.		7101-0749 5081-4968	1	Bottom Cover	28480	1
		201-4700		Rear Cover with Lettering (1157)	28480	]
	• ]	5081-4969	1'	Rear Cover, 230V	20400	
	l	, j		(Option 028)	28480	İ
	Į.	i	-	j	ļ	
	<u>l</u>			i	Ī	ļ

Teble 6-4. 6218/148/168/188/ Parts List (cont.)


Ref Desig	HP Part No	Qty	Description	Hfr Code	Hfr Pert No
6212B 6214B 6216B 6218B	06212-60004 06214-60004 06216-60004 06218-60004	1 1 1 1	Front Cover with Lettering	28480 28480 28480 28480	
6212B 6214B 6216B 6218B	06212-60002 06214-60002 06216-60002 06218-60002	1 1 1	Front Panel Assembly	28480 28480 28480 28480	·
6212B 6214B 6216B 6218B	1120-1247 1120-1133 1120-1137 1120-1142 4040-0934 1460-0256 5020-5757 5020-5731	1 1 1 1 1 1 1	Heters 2.25A, 120V 2.25A, 12V 2.25A, 30V 2.25A, 60V Meter Bezel Heter Spring Al Board (Blank) A2 Board (Blank)	28480 28480 28480 28480 28480 28480 28480 28480	;
62128 62148 62168 62188	06212-60020 06214-60020 06216-60020 06218-60020	1 1	Al Board with Components	28480 28480 28480 28480 28480	
62128 6214B 6216B \ 6218B	06212-60021 06214-60021 06216-60021 06218-60021	1 1 1 1	A2 Board with Components	28480 28480 28480 28480	•
**	5950-1928 9211-3319 9220-3212 9220-3213	1 1 2	Operating & Service Manual Corrugated Container Corrugated Pad Foam Pad	28480 28480 28480 28480	


# SCHEMATIC DIAGRAMS

# Section VII CIRCUIT DIAGRAMS

This section contains the circuit diagrams necessary for the operation and maintenance of these power supplies. Included are:

- a. Component Location Diagram, Figure 7-1 and 7-2 show the physical location and reference designator of parts mounted on the printed wir-
- ing board.
- b. Schematic Diagram, figure 7-3, which illustrates the circuitry for the entire power supply. Voltages are given adjacent to test points, identified by encircled numbers on the schematic and printed wiring board.







A2 FRONT PANEL BOARD (rear view)

Figure 7-1. Component Location Diagram Model 6212B

## A1 MAIN BOARD





A2 FRONT PANEL BOARD (rear view)

Figure 7-2. Component Location Diagram. Models 6214B, 6216B, 6218B

#### \*COMPONENT VALUE TABLE.

NAME OF THE STREET OF THE STRE								
COMPONENT								
	6212B	62148	<b>6216B</b>	6218B				
C1 C L15 R1 R6 R8 R10A R10B R11A R11B R12 R14 R17 R19 R20 R21 R22 R26 R28 R30 R31 R33 R33 R42 R52 R53 R54 R55 R55 R55	5µF 150 V ,0047 µF 10% ,001 µF 10% ,001 µF 10% ,001 µF 10% ,001 Used 3 k ±5% 5 W 4.75 k 1% ,75 5% 22 k - 200 3 k - 50 5 k - 50 1124 ± 1.1% 125 W 82 k 5% .5 W 10 k 5% .5 W 22 0 5% .5 W 220 5% .5 W 26 6% .5 W 160 5% .5 W 160 5% .5 W 160 5% .5 W 160 5% .5 W 17 k 5% .5 W 18 5% .5 W 18 5% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 18 6% .5 W 19 6% .125 W 10 6% 3 W 23 k 1% .125 W 19 1% .125 W 19 1% .125 W 19 1% .125 W	5µF 50 V .0068 µF 10% .0047 µF 10% 3.3 µF ± 10% 50 V 1 k ± 3% 3 W 1.5 k 1% 24 5% 5 k - 50 5 k - 50 5 k - 50 2.6 k ± 5% 3 W 3.3 5% .5 W 6.2 \times 5.5 W 820 5% .5 W 820 5% .5 W 200 6% .5 W 820 5% .5 W 820 6% .5 W	5 µF 65 V .0068 µF 10% .0047 µF 10% 3.3 µF ± 10% 50 V 1 k ±5% 3 W 1.5 k 1% 24 5% 5 k - 50 5 k - 60 10 k - 100 10 k - 100 1 k ±5% 3 W 3.3 5% .5 W 7.5 k 5% .5 W 2 k 5% 2 W 240 5% .5 W 200 5% .5 W 820 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 2 k 5% .5 W 2 k 5% .5 W 200 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 200 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 200 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 200 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 200 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 1 k 5% .5 W 3 k 5% .5 W 1 k 5% .5 W 3 k 5% .5 W 1 k 5% .5 W 3 k 5% .5 W 1 k 5% .5 W 3 k 5% .5 W 1 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 3 k 5% .5 W 4 k 5% .5 W 4 k 5% .5 W 4 k 5% .5 W 4 k 5% .5 W 4 k 5% .5 W 5 k 1% .125 W 3 k 1% .125 W	5 µF 65 V 10047 µF 10047 µF 10% 6 µF + 76 - 10% 65 V 1 k ± 5% 3 W 1.5 k 1% 24 5% 5 k - 50 5 k - 50 5 k - 50 6 k - 50 6 k - 50 7 k - 50 8 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 2 k 5% 5 W 45 k 5% 5 W 1 k 5% 5 W 1 k 5% 5 W 2 k 5% 3 W 45 k 1% .125 W 45 k 1% .125 W 200 4 k 1% .125 W 200 4 k 1% .125 W 200 5% 125 W				

- All resistors are 1/2 W, 5% unless otherwise specified.
   All 1/8 and 1/4 watt resistors are 1%, 100 ppm.

- 220 ppm wire temperature coefficient.

  Meter switch, S2, as viewed from rear. Shown in voltage position.
- Denotes voltage feedback signal
  Denotes current feedback signal.
- Transformer shown strapped for 115 V operation. See instruction manual for 220 Vac.
- DC voltages were measured under the following conditions:

  A. Hawlett Packard voltmeter Model 3456A or 3466/i or equivalent.
- 8. 115 Vac input.
- C. Voltages referenced to + S unless otherwise noted.
- D. Voltages are typical, ± 10%, unless otherwise noted.

  E. All readings taken in constant voltage operation at maximum rated output with no load connected. and current control turned fully clockwise.
- Main supply output voltages are:

MODEL 6212B 6214B 62168 62188

10. Connect to proper pin number, see chart below.

MODEL	TI SECONDARY PIN NO.			
	. 8	9 '		
6212B				
62148	,			
6216B	(See Inset)			
62188	,			
	` . · · · · · · · · · · · · · · · · · ·	Į.		

11. This circuit is used in Model 6212B only. When in use delete the lines that connect points A and B and point C with test point 6






Figure 7-3. \ hematic Diagram.