



Ground Continuity Test Instrument Model M25 Model M30 Model M35

Safe, Fast, Efficient

- Performs ground continuity tests in full compliance with BSI, VDE, and IEC
- Test time is adjustable from 1 second to 90 seconds
- Measures AC resistance from chassis of Device Under Test (DUT) to power-cord ground lead— 0 to 0.15Ω
- Audible and visual alarms identify faulty ground connections
- Hipot interface enables interconnecting to any ROD-L Hipot Test Instrument to form an automatic test system
- AC power source supplies 25, 30, or 35 Amps (user specified) at ≈ 2.5 volts

ROD-L Hipot Test Systems Interfacing

- the Ground Continuity Test Instrument can be interconnected with any Rod-L Hipot Test Instrument to operate as a fully automatic system
- one connection for DUT, and one start button to press

SUPERIOR SAFETY FEATURES

- front panel receptacle is rated to 8000 VAC
- front panel receptacle prevents direct operator exposure to high voltage during test



Production/Quality Assurance Testing

- after test parameters are preset, a single button actuates the Fully Automatic test cycle
- measures ground continuity from chassis ground to the power cord ground pin of the DUT
- detects and indicates the following:
 - Test in Progress
 - Test Failed
 - Resistance measurement, 0-0.15Ω
 - · Current measurement in amperes
- ground resistance trip point easily preset via rear panel potentiometer
- if the ground resistance exceeds the preset value, a fail is indicated both audibly and visually



Specifications



Output Current

10, 25, 30, or 35 amperes, user specified

Resistance

0 to 0.15 Ω , accurate to \pm 5%, F.S.

Test Time

1 second to 90 seconds, user adjustable (5 to 7 seconds – standard factory setting)

Input Power Required

115/230 VAC, ±10%, 44-66 Hz,

360 watts maximum

Dimensions

16.75" x 5.25" x 13.25" (43 cm x 13 cm x 34 cm)

Weight

30 lbs (13.6 kg) Net

35 lbs (15.9 kg) Shipping

Color

Mint Grey/Black

OPTIONS

- 01 Remote Control (Digital)
- 06 Rear Panel Lockout Cover
- 10 Audible Testing Tone
- 15 Rack Mounting
- 19 Remote Control (Analog & Digital)
- 24 Blank Front Panel (Receptacle and/or Start)

OTHER ROD-L PRODUCTS

- M100/M500 Series AC Hipot Test Instruments
- M150AC AC Hipot Test Instrument
- M100DC DC Hipot Test Instrument
- M120DC DC Hipot Test Instrument
- M300RT DC Insulation Resistance Test Instrument
- M450 Leakage Current Test Instrument
- M650 High Voltage Switching Matrix
- M900 International Receptacle Adaptor
- M950 Hands-Off Controller
- M1088 IEEE 488 Bus Interface Adaptor
- M2000 Series Safety Control Cabinet
- ML11, 12 Test Loads
- MP21 Probe





OPTIONALLY

IEEE 488